

BID NUMBER # 26116 - Rolling Road Force Main Replacement

Addendum 2

The below Bidding/Bidder Questions were received several hours after the deadline for questions. LCPW has decided to provide responses for these questions, for this project.

1. Bidding/Bidder Question

Q1: In the Directional Drilling and HDPE Piping specification 33 41 50 (3.03 B) Testing section you are calling for the following: Contractor shall test the HDPE pipe and fittings for acceptable passage of a pipe cleaning PIG. Can you clarify what you will be looking for for this? What are the requirements for this?

R1: Testing requirements are outlined in Technical Specification Section 33 41 50 and states that Hydrostatic pressure testing shall be conducted in accordance with the manufacturer's recommended procedure. Pneumatic (air) testing is prohibited. Contingent to the award of Alternative #1 Bid, Contractor shall test the HDPE pipe and fittings for acceptable passage of an appropriately sized pipe cleaning PIG.

2. Bidding/Bidder Question

Q1: For the sewer connection to the existing drop structure, you are calling for the contractor to repair / line the drop structure with a Neopoxy Coating System. Can you clarify the limits of the coating system, what exactly will need to be coated? Will the entire structure need to be coated or just the area that the contractors disturbs while making the connection?

R1: Please refer to the response provided in Addendum 1.

3. Bidding/Bidder Question

Q1: For the directional drilling of the force main along Rollins Road will we be able to close down the shoulder of Rollins Road for the duration of the work. Please clarify if LCDOT will allow this.

R1: Please refer to the response provided in Addendum 1. See Restoration Guarantee note on Page 4 under Special Conditions For Construction Within a Lake County Highway Right-of-Way. All traffic control shall be included under the Lump Sum Line Item No. 7 in the Bid Form.

4. Bidding/Bidder Question

Q1: Finally per talking with the pipe suppliers for the piping and fittings required for the project we are being told that some of the material has a 16 - 18 week lead time. Due to the lead time we would not be able to meet the interim completion date of 100 calendar days for the work between Sta. 116+00 to Sta. 110+00. Can the interim completion date be changed to accommodate the lead time to procure the material?

R1: We anticipate that this substantial completion duration can be met for the work within the extents of Sta. 116+00 to Sta. 100+00.

Please note, recently a Fiber Optic Cable was installed in the southern shoulder of Rollins Road, off of the east bound lane, subsequent to when the drawings were prepared.

END OF ADDENDUM 2