

ADDENDUM NO. 3
TO THE CONTRACT DOCUMENTS
FOR THE CONSTRUCTION OF THE
VERNON HILLS NCT WRF PHASE 2 – 2017 IMPROVEMENTS
LAKE COUNTY PUBLIC WORKS DEPARTMENT
VERNON HILLS, ILLINOIS
BID NUMBER #17013

DATE: April 14, 2017

BID DATE: 2:00 P.M. Local Time, April 18, 2017 (REVISED)

TO ALL BIDDERS ON THE ABOVE PROJECT:

The following changes, additions and deletions are hereby made a part of the Contract Documents for the Vernon Hills NCT WRF Phase 2 – 2017 Improvements, Lake County Public Works Department, Vernon Hills, Illinois Bid Number #17013 as fully and completely as if the same were fully set forth therein.

Bidders shall acknowledge receipt of this Addendum by inserting the number and date in the space provided in the Bid Form.

SPECIFICATIONS

SECTION 16111 – CONDUITS

1. Paragraph 3.3 K.

Revise this paragraph to read as follows:

- K. Secure conduit in place with 316 stainless steel straps, hangers and hardware including all aluminum conduit located in “Battery A” and “Battery B” digesters. Conduit straps used on PVC coated conduit shall be PVC coated and conduit straps used on aluminum conduit shall be aluminum or 316 stainless steel.*

SECTION 16190 – SUPPORTING DEVICES

1. Paragraph 2.2 A.

Revise this paragraph to read as follows:

- A. *For interior spaces: Metal supporting devices shall be zinc galvanized or cadmium plated steel or malleable iron.*
- B. *For interior spaces that are corrosive, and supports located in “Battery A” and “Battery B” digesters: Supporting devices shall be FRP or 316 stainless steel. Fastening hardware shall be 316 stainless steel.*
- C. *For aluminum conduit: Supporting devices shall be aluminum, FRP or 316 stainless steel. Fastening hardware shall be 316 stainless steel.*
- D. *Provide anchor bolts, concrete anchors, and masonry anchors as specified in Section 05500.*