

Bid Item #	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
	GENERAL REQUIREMENTS				
1	Mobilization / Project Administration / Demobilization <b>Division 1</b>	LS	1		
2	Testing Laboratory Services (Allowance)	LS	1		\$ 4,000
	EXISTING CONDITIONS				
3	Perimeter Chain Link Construction Fencing Including Three Gates	LS	1		
4	Silt Fence	LS	1		
5	Stabilized Construction Entrance	EA	1		
6	Tree Root Bridging Protection and Removal of Existing Shrubs as Required	LS	1		
7	Root Pruning of Existing Tree #448, #449 and #452	EA	3		
8	Demolition of Existing Sidewalks and Generator Pad Including All Saw Cutting and Disposal	LS	1		
	<b>Division 2</b>	LS	1		
	CONCRETE				
9	Generator Pad	LS	1		
10	Service Walk	LS	1		
11	Core Building Wall for 10" Water Main Piping	EA	1		
12	Core Building Wall for 4" Sump Pump Drain Line	EA	1		
	<b>Division 3</b>	LS	1		
	PAINTING				
13	Paint New Exterior Gas Piping / Fittings <b>Division 9</b>	LS	1		
	PLUMBING				
14	1/2" Copper Supply to Chlorine Analyzer Equipment Including Solenoid Valve	LS	1		
15	2" PVC Drain Line for Chlorine Analyzer Equipment	LS	1		
16	4" PVC Exterior Drain Line for Sump Pump	LS	1		
17	Cored Connection to Existing Manhole including Pipe Boot for 4" PVC Drain Line	EA	1		
18	6" / 8" / 10" DIP CL-53 Flanged Interior Water Piping and Fittings	LS	1		
19	10" DIP CL-52 MJ Exterior Water Piping and Fittings	LS	1		
20	Wall Sleeve and Link Seal at Building Wall Penetration for 10" Pipe	EA	1		
21	Wall Sleeve and Link Seal at Building Wall Penetration for 4" Pipe	EA	1		
22	6" Motorized BF Valve	EA	1		
23	8" BF Valve with Chain Wheel	EA	1		
24	8" Pressure Sustaining Valve	EA	1		
25	Steel Column Pipe Supports	EA	2		
26	Sampling Sink Including Required Piping	LS	1		
	<b>Division 22</b>	LS	1		
	HVAC				
27	Demolition of Existing Exterior Natural Gas Piping	LS	1		
28	Existing Generator Removal / Salvage / Turn Over to Owner	LS	1		
29	Natural Gas Piping	LS	1		
	<b>Division 23</b>	LS	1		
	ELECTRICAL				
30	Conduit, Boxes and Wiring for Motorized 6" Valve	LS	1		
31	Conduit, Boxes and Wiring for Pressure Sustaining Valve and Pressure Transmitter	LS	1		
32	Conduit, Boxes, Plugs and Wiring for Chlorine Analyzer	LS	1		
33	Conduit, Boxes and Wiring for Flow Meter	LS	1		
34	Conduit, Boxes and Wiring for Generator	LS	1		
35	150 KW Natural Gas Generator Set	EA	1		
	<b>Division 26</b>	LS	1		
	EARTHWORK				
36	Excavation / Bedding / Backfill / Compaction for 10" Water Piping	LS	1		
37	Excavation / Bedding / Backfill / Compaction for 4" PVC Drain Line	LS	1		
38	Excavation / Bedding / Backfill / Compaction for Electrical Piping	LS	1		
39	Excavation / Bedding / Backfill / Compaction for Gas Piping	LS	1		
40	Excavation / Bedding / Backfill / Compaction for Concrete Flat Work	LS	1		
	<b>Division 31</b>	LS	1		
	LAWNS AND GRASSES				
41	Temporary Seeding / Excelsior Blanket / Watering <b>Division 32</b>	LS	1		
	PROCESS INTERCONNECTIONS				
42	Magnetic Flow Meter	EA	1		
43	Rework / Repurpose Existing Control Panel Circuitry (Limited to Available Spares)	LS	1		
	<b>Division 40</b>	LS	1		
	WATER TREATMENT EQUIPMENT				
44	Chlorine Analyzer <b>Division 44</b>	EA	1		
BID AMOUNT ITEMS 1 TO 44			TOTAL PHASE-1 \$		