

## Summary of Bids Received

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Bidder	Address	City, State, Zip	Bond	Bid Price	% Over/Under Eng. Estimate	\$ Over/Under Eng. Estimate
Berger Excavating Contractors	1205 Garland Road	Wauconda, IL 60084	Bid Bond	\$2,133,208.86	-26.33%	-\$762,304.09
Lake County Grading Company	32901 N. IL Rte 21	Libertyville, IL 60048	Bid Bond	\$2,233,445.50	-22.87%	-\$662,067.45
Campanella & Sons, Inc.	39207 N Magnetics Blvd	Wadsworth, IL 60083	Bid Bond	\$2,265,594.10	-21.76%	-\$629,918.85
Martam Construction, Inc.	1200 Gasket Drive	Elgin, IL 60120	Bid Bond	\$2,992,779.84	3.36%	\$97,266.89
Engineer's Estimate				\$2,895,512.95		

Design	_____	IDOT(2)	_____	Contract Bidder	_____	County Engineer	_____
Finance	_____	Bid Tab File	_____	Resident Eng.	_____	Mgr Capital Programming	_____
Construction	_____	Project File	_____	Request By Mail	_____		

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	626.0	UNIT	\$40.00	\$25,040.00	\$9.00	\$5,634.00	\$9.00	\$5,634.00	\$9.00	\$5,634.00	\$28.08	\$17,578.08
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	488.0	UNIT	\$40.00	\$19,520.00	\$11.00	\$5,368.00	\$11.00	\$5,368.00	\$11.00	\$5,368.00	\$40.56	\$19,793.28
3	20101100	TREE TRUNK PROTECTION	21.0	EACH	\$130.00	\$2,730.00	\$180.00	\$3,780.00	\$180.00	\$3,780.00	\$180.00	\$3,780.00	\$182.00	\$3,822.00
4	20101200	TREE ROOT PRUNING	21.0	EACH	\$100.00	\$2,100.00	\$90.00	\$1,890.00	\$90.00	\$1,890.00	\$90.00	\$1,890.00	\$156.00	\$3,276.00
5	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	14.0	EACH	\$75.00	\$1,050.00	\$40.00	\$560.00	\$40.00	\$560.00	\$40.00	\$560.00	\$130.00	\$1,820.00
6	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	7.0	EACH	\$100.00	\$700.00	\$120.00	\$840.00	\$120.00	\$840.00	\$120.00	\$840.00	\$182.00	\$1,274.00
7	20200100	EARTH EXCAVATION	12,327.0	CU YD	\$22.00	\$271,194.00	\$0.01	\$123.27	\$12.30	\$151,622.10	\$0.01	\$123.27	\$27.00	\$332,829.00
8	20400800	FURNISHED EXCAVATION	100.0	CU YD	\$50.00	\$5,000.00	\$30.00	\$3,000.00	\$74.90	\$7,490.00	\$0.01	\$1.00	\$87.60	\$8,760.00
9	20800150	TRENCH BACKFILL	340.0	CU YD	\$45.00	\$15,300.00	\$31.00	\$10,540.00	\$46.00	\$15,640.00	\$20.00	\$6,800.00	\$67.59	\$22,980.60
10	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	10,422.0	SQ YD	\$4.00	\$41,688.00	\$1.60	\$16,675.20	\$2.00	\$20,844.00	\$1.50	\$15,633.00	\$2.10	\$21,886.20
11	21101615	TOPSOIL FURNISH AND PLACE, 4"	14,365.0	SQ YD	\$4.50	\$64,642.50	\$0.01	\$143.65	\$4.00	\$57,460.00	\$1.20	\$17,238.00	\$4.16	\$59,758.40
12	21101805	COMPOST FURNISH AND PLACE, 2"	7,026.0	SQ YD	\$3.00	\$21,078.00	\$2.85	\$20,024.10	\$4.00	\$28,104.00	\$4.00	\$28,104.00	\$4.16	\$29,228.16
13	25000210	SEEDING, CLASS 2A	3.0	ACRE	\$2,500.00	\$7,500.00	\$2,960.00	\$8,880.00	\$3,000.00	\$9,000.00	\$3,000.00	\$9,000.00	\$3,120.00	\$9,360.00
14	25000400	NITROGEN FERTILIZER NUTRIENT	293.0	POUND	\$3.00	\$879.00	\$1.10	\$322.30	\$1.00	\$293.00	\$1.00	\$293.00	\$1.04	\$304.72
15	25000600	POTASSIUM FERTILIZER NUTRIENT	293.0	POUND	\$3.00	\$879.00	\$1.10	\$322.30	\$1.00	\$293.00	\$1.00	\$293.00	\$1.04	\$304.72
16	25100630	EROSION CONTROL BLANKET	14,223.0	SQ YD	\$1.00	\$14,223.00	\$1.10	\$15,645.30	\$1.65	\$23,467.95	\$1.65	\$23,467.95	\$1.72	\$24,463.56
17	25200200	SUPPLEMENTAL WATERING	28.0	UNIT	\$150.00	\$4,200.00	\$40.00	\$1,120.00	\$0.10	\$2.80	\$0.10	\$2.80	\$0.10	\$2.80
18	28000250	TEMPORARY EROSION CONTROL SEEDING	384.0	POUND	\$5.00	\$1,920.00	\$5.00	\$1,920.00	\$0.10	\$38.40	\$0.10	\$38.40	\$0.10	\$38.40
19	28000305	TEMPORARY DITCH CHECKS	238.0	FOOT	\$20.00	\$4,760.00	\$15.00	\$3,570.00	\$12.00	\$2,856.00	\$12.00	\$2,856.00	\$12.48	\$2,970.24

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60  
**Section:** 12-00138-02-CH  
**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation  
**CPMS Pin:** B-00474C  
**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
20	28000400	PERIMETER EROSION BARRIER	2,342.0	FOOT	\$3.00	\$7,026.00	\$3.00	\$7,026.00	\$3.00	\$7,026.00	\$3.00	\$7,026.00	\$3.12	\$7,307.04
21	28000510	INLET FILTERS	5.0	EACH	\$150.00	\$750.00	\$250.00	\$1,250.00	\$140.00	\$700.00	\$140.00	\$700.00	\$145.60	\$728.00
22	28001100	TEMPORARY EROSION CONTROL BLANKET	18,541.0	SQ YD	\$0.60	\$11,124.60	\$1.10	\$20,395.10	\$0.50	\$9,270.50	\$0.50	\$9,270.50	\$0.52	\$9,641.32
23	28100105	STONE RIPRAP, CLASS A3	46.0	SQ YD	\$40.00	\$1,840.00	\$100.00	\$4,600.00	\$82.50	\$3,795.00	\$100.00	\$4,600.00	\$57.45	\$2,642.70
24	28200200	FILTER FABRIC	58.0	SQ YD	\$8.00	\$464.00	\$4.00	\$232.00	\$4.00	\$232.00	\$2.00	\$116.00	\$7.35	\$426.30
25	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	10,390.0	SQ YD	\$14.00	\$145,460.00	\$14.00	\$145,460.00	\$19.03	\$197,721.70	\$18.00	\$187,020.00	\$14.30	\$148,577.00
26	35101800	AGGREGATE BASE COURSE, TYPE B 6"	231.0	SQ YD	\$9.00	\$2,079.00	\$9.65	\$2,229.15	\$12.74	\$2,942.94	\$11.00	\$2,541.00	\$8.62	\$1,991.22
27	35102000	AGGREGATE BASE COURSE, TYPE B 8"	459.0	SQ YD	\$10.00	\$4,590.00	\$12.25	\$5,622.75	\$14.75	\$6,770.25	\$12.00	\$5,508.00	\$11.94	\$5,480.46
28	35501315	HOT-MIX ASPHALT BASE COURSE, 7 3/4"	2,469.0	SQ YD	\$50.00	\$123,450.00	\$30.70	\$75,798.30	\$30.70	\$75,798.30	\$30.70	\$75,798.30	\$32.11	\$79,279.59
29	40201000	AGGREGATE FOR TEMPORARY ACCESS	218.0	TON	\$40.00	\$8,720.00	\$19.00	\$4,142.00	\$25.55	\$5,569.90	\$0.01	\$2.18	\$25.13	\$5,478.34
30	40600290	BITUMINOUS MATERIALS (TACK COAT)	8,973.0	POUND	\$1.00	\$8,973.00	\$0.01	\$89.73	\$0.01	\$89.73	\$0.01	\$89.73	\$0.01	\$89.73
31	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	10.0	TON	\$300.00	\$3,000.00	\$75.00	\$750.00	\$75.00	\$750.00	\$75.00	\$750.00	\$78.44	\$784.40
32	40600525	LEVELING BINDER (HAND METHOD), N50	5.0	TON	\$120.00	\$600.00	\$75.00	\$375.00	\$75.00	\$375.00	\$75.00	\$375.00	\$78.43	\$392.15
33	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	68.0	SQ YD	\$20.00	\$1,360.00	\$10.00	\$680.00	\$10.00	\$680.00	\$10.00	\$680.00	\$10.46	\$711.28
34	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	1,464.0	TON	\$80.00	\$117,120.00	\$69.00	\$101,016.00	\$69.00	\$101,016.00	\$69.00	\$101,016.00	\$72.16	\$105,642.24
35	40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	827.0	TON	\$100.00	\$82,700.00	\$84.20	\$69,633.40	\$84.20	\$69,633.40	\$84.20	\$69,633.40	\$88.06	\$72,825.62
36	40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	514.0	TON	\$100.00	\$51,400.00	\$82.10	\$42,199.40	\$82.10	\$42,199.40	\$82.10	\$42,199.40	\$85.86	\$44,132.04
37	40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	654.0	TON	\$100.00	\$65,400.00	\$80.00	\$52,320.00	\$80.00	\$52,320.00	\$80.00	\$52,320.00	\$83.66	\$54,713.64

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60  
**Section:** 12-00138-02-CH  
**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation  
**CPMS Pin:** B-00474C  
**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
38	42001300	PROTECTIVE COAT	569.0	SQ YD	\$1.50	\$853.50	\$5.00	\$2,845.00	\$5.00	\$2,845.00	\$0.01	\$5.69	\$2.13	\$1,211.97
39	44000100	PAVEMENT REMOVAL	2,714.0	SQ YD	\$15.00	\$40,710.00	\$7.75	\$21,033.50	\$5.50	\$14,927.00	\$8.00	\$21,712.00	\$11.32	\$30,722.48
40	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	1,760.0	SQ YD	\$4.50	\$7,920.00	\$4.70	\$8,272.00	\$4.70	\$8,272.00	\$4.70	\$8,272.00	\$4.92	\$8,659.20
41	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	4,421.0	SQ YD	\$4.50	\$19,894.50	\$3.00	\$13,263.00	\$3.00	\$13,263.00	\$3.00	\$13,263.00	\$3.14	\$13,881.94
42	44000200	DRIVEWAY PAVEMENT REMOVAL	662.0	SQ YD	\$13.00	\$8,606.00	\$6.25	\$4,137.50	\$3.06	\$2,025.72	\$4.00	\$2,648.00	\$11.04	\$7,308.48
43	44004250	PAVED SHOULDER REMOVAL	1,001.0	SQ YD	\$10.00	\$10,010.00	\$8.00	\$8,008.00	\$5.50	\$5,505.50	\$4.00	\$4,004.00	\$10.37	\$10,380.37
44	44201773	CLASS D PATCHES, TYPE I, 11 INCH	10.0	SQ YD	\$90.00	\$900.00	\$40.00	\$400.00	\$40.00	\$400.00	\$40.00	\$400.00	\$56.56	\$565.60
45	44201777	CLASS D PATCHES, TYPE II, 11 INCH	31.0	SQ YD	\$90.00	\$2,790.00	\$40.00	\$1,240.00	\$40.00	\$1,240.00	\$40.00	\$1,240.00	\$56.47	\$1,750.57
46	44201781	CLASS D PATCHES, TYPE III, 11 INCH	68.0	SQ YD	\$90.00	\$6,120.00	\$40.00	\$2,720.00	\$40.00	\$2,720.00	\$40.00	\$2,720.00	\$56.42	\$3,836.56
47	44201783	CLASS D PATCHES, TYPE IV, 11 INCH	68.0	SQ YD	\$90.00	\$6,120.00	\$40.00	\$2,720.00	\$40.00	\$2,720.00	\$40.00	\$2,720.00	\$56.42	\$3,836.56
48	48101200	AGGREGATE SHOULDERS, TYPE B	213.0	TON	\$45.00	\$9,585.00	\$43.80	\$9,329.40	\$31.00	\$6,603.00	\$43.80	\$9,329.40	\$59.46	\$12,664.98
49	48203100	HOT-MIX ASPHALT SHOULDERS	1,841.0	TON	\$85.00	\$156,485.00	\$64.60	\$118,928.60	\$64.60	\$118,928.60	\$64.60	\$118,928.60	\$67.56	\$124,377.96
50	50104400	CONCRETE HEADWALL REMOVAL	2.0	EACH	\$500.00	\$1,000.00	\$2,850.00	\$5,700.00	\$650.00	\$1,300.00	\$1,000.00	\$2,000.00	\$346.68	\$693.36
51	54002020	EXPANSION BOLTS 3/4 INCH	8.0	EACH	\$30.00	\$240.00	\$415.00	\$3,320.00	\$15.00	\$120.00	\$0.01	\$0.08	\$158.47	\$1,267.76
52	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	2.0	EACH	\$400.00	\$800.00	\$1,540.00	\$3,080.00	\$1,595.00	\$3,190.00	\$2,000.00	\$4,000.00	\$721.76	\$1,443.52
53	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	12.0	EACH	\$450.00	\$5,400.00	\$1,590.00	\$19,080.00	\$1,850.00	\$22,200.00	\$2,000.00	\$24,000.00	\$752.50	\$9,030.00
54	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	1.0	EACH	\$500.00	\$500.00	\$1,675.00	\$1,675.00	\$1,975.00	\$1,975.00	\$2,000.00	\$2,000.00	\$810.64	\$810.64
55	54248510	CONCRETE COLLAR	0.3	CU YD	\$763.00	\$228.90	\$26,500.00	\$7,950.00	\$5,750.00	\$1,725.00	\$5,000.00	\$1,500.00	\$3,202.97	\$960.89
56	54260515	SLOPED METAL END SECTION, STANDARD 542411, 15", 1:6	2.0	EACH	\$150.00	\$300.00	\$1,050.00	\$2,100.00	\$1,065.00	\$2,130.00	\$500.00	\$1,000.00	\$1,878.49	\$3,756.98

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
57	54260521	SLOPED METAL END SECTION, STANDARD 542411, 21", 1:6	3.0	EACH	\$200.00	\$600.00	\$1,350.00	\$4,050.00	\$1,575.00	\$4,725.00	\$1,100.00	\$3,300.00	\$1,878.50	\$5,635.50
58	542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	27.0	FOOT	\$50.00	\$1,350.00	\$53.50	\$1,444.50	\$55.25	\$1,491.75	\$40.00	\$1,080.00	\$91.46	\$2,469.42
59	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	15.0	FOOT	\$75.00	\$1,125.00	\$68.00	\$1,020.00	\$42.50	\$637.50	\$50.00	\$750.00	\$88.13	\$1,321.95
60	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	145.0	FOOT	\$80.00	\$11,600.00	\$50.65	\$7,344.25	\$45.80	\$6,641.00	\$55.00	\$7,975.00	\$77.98	\$11,307.10
61	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	80.0	FOOT	\$80.00	\$6,400.00	\$57.00	\$4,560.00	\$44.10	\$3,528.00	\$42.00	\$3,360.00	\$74.65	\$5,972.00
62	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	705.0	FOOT	\$80.00	\$56,400.00	\$50.50	\$35,602.50	\$48.00	\$33,840.00	\$46.00	\$32,430.00	\$83.82	\$59,093.10
63	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	21.0	FOOT	\$90.00	\$1,890.00	\$165.00	\$3,465.00	\$133.00	\$2,793.00	\$149.00	\$3,129.00	\$117.81	\$2,474.01
64	55100100	STORM SEWER REMOVAL 4"	22.0	FOOT	\$10.00	\$220.00	\$15.00	\$330.00	\$11.00	\$242.00	\$12.00	\$264.00	\$11.78	\$259.16
65	55100500	STORM SEWER REMOVAL 12"	849.0	FOOT	\$12.00	\$10,188.00	\$15.00	\$12,735.00	\$15.50	\$13,159.50	\$15.00	\$12,735.00	\$11.75	\$9,975.75
66	55100700	STORM SEWER REMOVAL 15"	307.0	FOOT	\$15.00	\$4,605.00	\$20.00	\$6,140.00	\$17.00	\$5,219.00	\$15.00	\$4,605.00	\$11.75	\$3,607.25
67	55100900	STORM SEWER REMOVAL 18"	165.0	FOOT	\$18.00	\$2,970.00	\$20.00	\$3,300.00	\$17.00	\$2,805.00	\$15.00	\$2,475.00	\$11.74	\$1,937.10
68	60100905	PIPE DRAINS 4"	100.0	FOOT	\$30.00	\$3,000.00	\$20.50	\$2,050.00	\$19.50	\$1,950.00	\$0.01	\$1.00	\$28.58	\$2,858.00
69	60100915	PIPE DRAINS 6"	100.0	FOOT	\$35.00	\$3,500.00	\$24.00	\$2,400.00	\$21.50	\$2,150.00	\$0.01	\$1.00	\$28.58	\$2,858.00
70	60108104	PIPE UNDERDRAINS, TYPE 1, 4"	5,277.0	FOOT	\$15.00	\$79,155.00	\$3.25	\$17,150.25	\$3.90	\$20,580.30	\$4.00	\$21,108.00	\$28.58	\$150,816.66
71	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	1.0	EACH	\$3,500.00	\$3,500.00	\$2,400.00	\$2,400.00	\$2,600.00	\$2,600.00	\$3,200.00	\$3,200.00	\$2,938.99	\$2,938.99
72	60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	1.0	EACH	\$4,500.00	\$4,500.00	\$3,450.00	\$3,450.00	\$3,900.00	\$3,900.00	\$4,200.00	\$4,200.00	\$3,546.38	\$3,546.38
73	60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	1.0	EACH	\$2,000.00	\$2,000.00	\$2,950.00	\$2,950.00	\$1,610.00	\$1,610.00	\$2,700.00	\$2,700.00	\$1,860.95	\$1,860.95
74	60207000	CATCH BASINS, TYPE C, TYPE 8 GRATE	1.0	EACH	\$2,000.00	\$2,000.00	\$1,225.00	\$1,225.00	\$1,510.00	\$1,510.00	\$2,600.00	\$2,600.00	\$1,750.28	\$1,750.28
75	60207005	CATCH BASINS, TYPE C, TYPE 1 FRAME, CLOSED LID	9.0	EACH	\$2,000.00	\$18,000.00	\$1,725.00	\$15,525.00	\$1,590.00	\$14,310.00	\$2,700.00	\$24,300.00	\$1,860.92	\$16,748.28

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
76	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	3.0	EACH	\$2,000.00	\$6,000.00	\$1,550.00	\$4,650.00	\$1,725.00	\$5,175.00	\$2,700.00	\$8,100.00	\$1,905.64	\$5,716.92
77	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	3.0	EACH	\$3,500.00	\$10,500.00	\$2,125.00	\$6,375.00	\$2,500.00	\$7,500.00	\$3,200.00	\$9,600.00	\$2,892.70	\$8,678.10
78	60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	3.0	EACH	\$4,100.00	\$12,300.00	\$4,350.00	\$13,050.00	\$3,600.00	\$10,800.00	\$4,400.00	\$13,200.00	\$3,805.00	\$11,415.00
79	60257900	MANHOLES TO BE RECONSTRUCTED	1.0	EACH	\$1,500.00	\$1,500.00	\$985.00	\$985.00	\$2,150.00	\$2,150.00	\$1,000.00	\$1,000.00	\$1,386.69	\$1,386.69
80	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	1.0	EACH	\$400.00	\$400.00	\$650.00	\$650.00	\$820.00	\$820.00	\$260.00	\$260.00	\$493.63	\$493.63
81	60500040	REMOVING MANHOLES	2.0	EACH	\$500.00	\$1,000.00	\$600.00	\$1,200.00	\$800.00	\$1,600.00	\$500.00	\$1,000.00	\$1,040.02	\$2,080.04
82	60500050	REMOVING CATCH BASINS	1.0	EACH	\$500.00	\$500.00	\$600.00	\$600.00	\$800.00	\$800.00	\$500.00	\$500.00	\$1,040.06	\$1,040.06
83	60500060	REMOVING INLETS	2.0	EACH	\$250.00	\$500.00	\$325.00	\$650.00	\$500.00	\$1,000.00	\$300.00	\$600.00	\$520.03	\$1,040.06
84	60600095	CLASS SI CONCRETE (OUTLET)	3.0	CU YD	\$750.00	\$2,250.00	\$765.00	\$2,295.00	\$765.00	\$2,295.00	\$425.00	\$1,275.00	\$927.00	\$2,781.00
85	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	1,123.0	FOOT	\$28.00	\$31,444.00	\$23.50	\$26,390.50	\$23.50	\$26,390.50	\$28.75	\$32,286.25	\$29.56	\$33,195.88
86	60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	603.0	FOOT	\$28.00	\$16,884.00	\$23.50	\$14,170.50	\$23.50	\$14,170.50	\$31.60	\$19,054.80	\$29.56	\$17,824.68
87	61101013	STORM SEWERS PROTECTED, CLASS A, 12"	370.0	FOOT	\$75.00	\$27,750.00	\$46.50	\$17,205.00	\$45.00	\$16,650.00	\$37.00	\$13,690.00	\$88.13	\$32,608.10
88	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	796.0	FOOT	\$30.00	\$23,880.00	\$33.50	\$26,666.00	\$35.00	\$27,860.00	\$35.00	\$27,860.00	\$36.40	\$28,974.40
89	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	1.0	EACH	\$3,000.00	\$3,000.00	\$3,500.00	\$3,500.00	\$3,800.00	\$3,800.00	\$3,800.00	\$3,800.00	\$3,952.00	\$3,952.00
90	63200310	GUARDRAIL REMOVAL	714.0	FOOT	\$10.00	\$7,140.00	\$5.00	\$3,570.00	\$6.50	\$4,641.00	\$6.50	\$4,641.00	\$6.76	\$4,826.64
91	66900200	NON-SPECIAL WASTE DISPOSAL	300.0	CU YD	\$75.00	\$22,500.00	\$77.00	\$23,100.00	\$83.00	\$24,900.00	\$0.01	\$3.00	\$78.00	\$23,400.00
92	66900530	SOIL DISPOSAL ANALYSIS	3.0	EACH	\$1,800.00	\$5,400.00	\$1,500.00	\$4,500.00	\$1,500.00	\$4,500.00	\$0.01	\$0.03	\$1,289.60	\$3,868.80

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60  
**Section:** 12-00138-02-CH  
**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation  
**CPMS Pin:** B-00474C  
**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
93	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	1.0	L SUM	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00	\$0.01	\$0.01	\$2,600.00	\$2,600.00
94	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	1.0	L SUM	\$3,000.00	\$3,000.00	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00	\$0.01	\$0.01	\$1,976.00	\$1,976.00
95	66901006	REGULATED SUBSTANCES MONITORING	5.0	CAL DA	\$900.00	\$4,500.00	\$1,000.00	\$5,000.00	\$1,000.00	\$5,000.00	\$0.01	\$0.05	\$863.20	\$4,316.00
96	67100100	MOBILIZATION	1.0	LSUM	\$170,000.00	\$170,000.00	\$127,000.00	\$127,000.00	\$84,500.00	\$84,500.00	\$134,000.00	\$134,000.00	\$178,686.65	\$178,686.65
97	70106800	CHANGEABLE MESSAGE SIGN	18.0	CAL M	\$800.00	\$14,400.00	\$700.00	\$12,600.00	\$700.00	\$12,600.00	\$700.00	\$12,600.00	\$728.00	\$13,104.00
98	70300100	SHORT TERM PAVEMENT MARKING	1,119.0	FOOT	\$0.75	\$839.25	\$0.30	\$335.70	\$0.30	\$335.70	\$0.30	\$335.70	\$0.31	\$346.89
99	70300150	SHORT TERM PAVEMENT MARKING REMOVAL	374.0	SQ FT	\$1.00	\$374.00	\$1.00	\$374.00	\$1.00	\$374.00	\$1.00	\$374.00	\$4.00	\$1,496.00
100	70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	219.0	SQ FT	\$0.25	\$54.75	\$1.00	\$219.00	\$1.00	\$219.00	\$1.00	\$219.00	\$1.56	\$341.64
101	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	25,431.0	FOOT	\$0.25	\$6,357.75	\$0.20	\$5,086.20	\$0.20	\$5,086.20	\$0.20	\$5,086.20	\$0.31	\$7,883.61
102	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	2,357.0	FOOT	\$0.30	\$707.10	\$0.24	\$565.68	\$0.24	\$565.68	\$0.24	\$565.68	\$0.42	\$989.94
103	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	731.0	FOOT	\$0.35	\$255.85	\$0.28	\$204.68	\$0.28	\$204.68	\$0.28	\$204.68	\$0.52	\$380.12
104	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	347.0	FOOT	\$0.65	\$225.55	\$0.65	\$225.55	\$0.65	\$225.55	\$0.65	\$225.55	\$0.73	\$253.31
105	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	121.0	FOOT	\$1.00	\$121.00	\$1.00	\$121.00	\$1.00	\$121.00	\$1.00	\$121.00	\$1.56	\$188.76
106	70300904	PAVEMENT MARKING TAPE, TYPE IV, 4"	1,699.0	FOOT	\$1.25	\$2,123.75	\$0.90	\$1,529.10	\$0.90	\$1,529.10	\$0.80	\$1,359.20	\$1.30	\$2,208.70
107	70400100	TEMPORARY CONCRETE BARRIER	1,464.0	FOOT	\$20.00	\$29,280.00	\$18.00	\$26,352.00	\$20.50	\$30,012.00	\$20.50	\$30,012.00	\$21.00	\$30,744.00
108	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	1,448.0	FOOT	\$8.00	\$11,584.00	\$3.25	\$4,706.00	\$4.25	\$6,154.00	\$4.25	\$6,154.00	\$8.00	\$11,584.00

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60  
**Section:** 12-00138-02-CH  
**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation  
**CPMS Pin:** B-00474C  
**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
109	70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	6.0	EACH	\$4,500.00	\$27,000.00	\$4,500.00	\$27,000.00	\$6,600.00	\$39,600.00	\$6,600.00	\$39,600.00	\$6,864.00	\$41,184.00
110	70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	5.0	EACH	\$500.00	\$2,500.00	\$2,000.00	\$10,000.00	\$2,350.00	\$11,750.00	\$2,350.00	\$11,750.00	\$2,444.00	\$12,220.00
111	72000100	SIGN PANEL - TYPE 1	30.0	SQ FT	\$25.00	\$750.00	\$56.30	\$1,689.00	\$57.00	\$1,710.00	\$26.17	\$785.10	\$31.20	\$936.00
112	72000200	SIGN PANEL - TYPE 2	26.0	SQ FT	\$30.00	\$780.00	\$57.10	\$1,484.60	\$58.00	\$1,508.00	\$57.10	\$1,484.60	\$62.40	\$1,622.40
113	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	7.0	EACH	\$70.00	\$490.00	\$40.00	\$280.00	\$40.00	\$280.00	\$40.00	\$280.00	\$72.80	\$509.60
114	72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	2.0	EACH	\$80.00	\$160.00	\$60.00	\$120.00	\$60.00	\$120.00	\$60.00	\$120.00	\$72.80	\$145.60
115	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	5.0	EACH	\$100.00	\$500.00	\$100.00	\$500.00	\$100.00	\$500.00	\$100.00	\$500.00	\$72.80	\$364.00
116	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	2.0	EACH	\$120.00	\$240.00	\$100.00	\$200.00	\$100.00	\$200.00	\$100.00	\$200.00	\$72.80	\$145.60
117	72800100	TELESCOPING STEEL SIGN SUPPORT	49.0	FOOT	\$15.00	\$735.00	\$9.50	\$465.50	\$9.50	\$465.50	\$9.50	\$465.50	\$18.72	\$917.28
118	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	219.0	SQ FT	\$5.00	\$1,095.00	\$4.00	\$876.00	\$4.00	\$876.00	\$4.00	\$876.00	\$4.16	\$911.04
119	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	9,367.0	FOOT	\$0.65	\$6,088.55	\$0.55	\$5,151.85	\$0.55	\$5,151.85	\$0.70	\$6,556.90	\$0.57	\$5,339.19
120	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	2,357.0	FOOT	\$0.75	\$1,767.75	\$0.60	\$1,414.20	\$0.60	\$1,414.20	\$0.90	\$2,121.30	\$0.62	\$1,461.34
121	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	379.0	FOOT	\$1.10	\$416.90	\$0.75	\$284.25	\$0.75	\$284.25	\$1.00	\$379.00	\$0.78	\$295.62
122	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	347.0	FOOT	\$2.25	\$780.75	\$1.00	\$347.00	\$1.00	\$347.00	\$2.00	\$694.00	\$1.04	\$360.88



## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
123	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	121.0	FOOT	\$5.00	\$605.00	\$4.00	\$484.00	\$4.00	\$484.00	\$4.00	\$484.00	\$4.16	\$503.36
124	78100100	RAISED REFLECTIVE PAVEMENT MARKER	80.0	EACH	\$33.00	\$2,640.00	\$50.00	\$4,000.00	\$50.00	\$4,000.00	\$60.00	\$4,800.00	\$52.00	\$4,160.00
125	78200005	GUARDRAIL REFLECTORS, TYPE A	7.0	EACH	\$50.00	\$350.00	\$11.00	\$77.00	\$10.00	\$70.00	\$10.00	\$70.00	\$10.40	\$72.80
126	78200011	BARRIER WALL REFLECTORS, TYPE C	44.0	EACH	\$10.00	\$440.00	\$6.00	\$264.00	\$6.00	\$264.00	\$6.00	\$264.00	\$15.60	\$686.40
127	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	44.0	EACH	\$10.00	\$440.00	\$15.00	\$660.00	\$15.00	\$660.00	\$15.00	\$660.00	\$25.88	\$1,138.72
128	78300202	PAVEMENT MARKING REMOVAL – WATER BLASTING	1,365.0	SQ FT	\$1.00	\$1,365.00	\$2.35	\$3,207.75	\$2.35	\$3,207.75	\$2.35	\$3,207.75	\$3.12	\$4,258.80
129	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	1,824.0	FOOT	\$20.00	\$36,480.00	\$19.50	\$35,568.00	\$19.50	\$35,568.00	\$19.50	\$35,568.00	\$20.28	\$36,990.72
130	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	424.0	FOOT	\$30.00	\$12,720.00	\$37.40	\$15,857.60	\$37.40	\$15,857.60	\$37.40	\$15,857.60	\$38.90	\$16,493.60
131	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	323.0	FOOT	\$40.00	\$12,920.00	\$57.00	\$18,411.00	\$57.00	\$18,411.00	\$57.00	\$18,411.00	\$59.28	\$19,147.44
132	81400100	HANDHOLE	1.0	EACH	\$1,500.00	\$1,500.00	\$1,401.00	\$1,401.00	\$1,401.00	\$1,401.00	\$1,401.00	\$1,401.00	\$1,457.04	\$1,457.04
133	81400200	HEAVY-DUTY HANDHOLE	7.0	EACH	\$2,000.00	\$14,000.00	\$1,792.00	\$12,544.00	\$1,792.00	\$12,544.00	\$1,792.00	\$12,544.00	\$1,863.68	\$13,045.76
134	81400300	DOUBLE HANDHOLE	1.0	EACH	\$2,800.00	\$2,800.00	\$2,480.00	\$2,480.00	\$2,480.00	\$2,480.00	\$2,480.00	\$2,480.00	\$2,579.20	\$2,579.20
135	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	1.0	EACH	\$2,000.00	\$2,000.00	\$420.00	\$420.00	\$420.00	\$420.00	\$420.00	\$420.00	\$436.80	\$436.80
136	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	1,732.0	FOOT	\$1.40	\$2,424.80	\$0.70	\$1,212.40	\$0.70	\$1,212.40	\$0.70	\$1,212.40	\$0.73	\$1,264.36
137	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	484.0	FOOT	\$1.40	\$677.60	\$1.20	\$580.80	\$1.20	\$580.80	\$1.20	\$580.80	\$1.25	\$605.00
138	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	1,380.0	FOOT	\$1.50	\$2,070.00	\$1.40	\$1,932.00	\$1.40	\$1,932.00	\$1.40	\$1,932.00	\$1.46	\$2,014.80

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60  
**Section:** 12-00138-02-CH  
**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation  
**CPMS Pin:** B-00474C  
**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
139	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	1,267.0	FOOT	\$1.60	\$2,027.20	\$1.70	\$2,153.90	\$1.70	\$2,153.90	\$1.70	\$2,153.90	\$1.77	\$2,242.59
140	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	1,019.0	FOOT	\$1.80	\$1,834.20	\$1.00	\$1,019.00	\$1.00	\$1,019.00	\$1.00	\$1,019.00	\$1.04	\$1,059.76
141	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	275.0	FOOT	\$3.50	\$962.50	\$3.20	\$880.00	\$3.20	\$880.00	\$3.20	\$880.00	\$3.33	\$915.75
142	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	1,161.0	FOOT	\$2.50	\$2,902.50	\$1.70	\$1,973.70	\$1.70	\$1,973.70	\$1.70	\$1,973.70	\$1.77	\$2,054.97
143	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	3.0	EACH	\$1,600.00	\$4,800.00	\$1,102.00	\$3,306.00	\$1,102.00	\$3,306.00	\$1,102.00	\$3,306.00	\$1,146.08	\$3,438.24
144	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	1.0	EACH	\$1,800.00	\$1,800.00	\$1,258.00	\$1,258.00	\$1,258.00	\$1,258.00	\$1,258.00	\$1,258.00	\$1,308.32	\$1,308.32
145	87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	1.0	EACH	\$11,000.00	\$11,000.00	\$8,870.00	\$8,870.00	\$8,870.00	\$8,870.00	\$8,870.00	\$8,870.00	\$9,224.80	\$9,224.80
146	87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	1.0	EACH	\$15,000.00	\$15,000.00	\$14,452.00	\$14,452.00	\$14,452.00	\$14,452.00	\$14,452.00	\$14,452.00	\$15,030.08	\$15,030.08
147	87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 32 FT.	1.0	EACH	\$16,000.00	\$16,000.00	\$14,683.00	\$14,683.00	\$14,683.00	\$14,683.00	\$14,683.00	\$14,683.00	\$15,270.32	\$15,270.32
148	87800100	CONCRETE FOUNDATION, TYPE A	21.0	FOOT	\$250.00	\$5,250.00	\$240.00	\$5,040.00	\$240.00	\$5,040.00	\$240.00	\$5,040.00	\$249.60	\$5,241.60
149	87800150	CONCRETE FOUNDATION, TYPE C	4.0	FOOT	\$600.00	\$2,400.00	\$662.00	\$2,648.00	\$662.00	\$2,648.00	\$662.00	\$2,648.00	\$688.48	\$2,753.92
150	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	10.0	FOOT	\$200.00	\$2,000.00	\$204.00	\$2,040.00	\$204.00	\$2,040.00	\$204.00	\$2,040.00	\$212.16	\$2,121.60
151	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	24.0	FOOT	\$250.00	\$6,000.00	\$215.00	\$5,160.00	\$215.00	\$5,160.00	\$215.00	\$5,160.00	\$223.60	\$5,366.40
152	87900200	DRILL EXISTING HANDHOLE	1.0	EACH	\$300.00	\$300.00	\$269.00	\$269.00	\$269.00	\$269.00	\$269.00	\$269.00	\$279.76	\$279.76
153	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	4.0	EACH	\$850.00	\$3,400.00	\$643.00	\$2,572.00	\$643.00	\$2,572.00	\$643.00	\$2,572.00	\$668.72	\$2,674.88

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
154	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	5.0	EACH	\$800.00	\$4,000.00	\$592.00	\$2,960.00	\$592.00	\$2,960.00	\$592.00	\$2,960.00	\$615.68	\$3,078.40
155	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	2.0	EACH	\$1,100.00	\$2,200.00	\$877.00	\$1,754.00	\$877.00	\$1,754.00	\$877.00	\$1,754.00	\$912.08	\$1,824.16
156	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	2.0	EACH	\$1,200.00	\$2,400.00	\$926.00	\$1,852.00	\$926.00	\$1,852.00	\$926.00	\$1,852.00	\$963.04	\$1,926.08
157	88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	6.0	EACH	\$200.00	\$1,200.00	\$254.00	\$1,524.00	\$254.00	\$1,524.00	\$254.00	\$1,524.00	\$264.16	\$1,584.96
158	88500100	INDUCTIVE LOOP DETECTOR	3.0	EACH	\$200.00	\$600.00	\$165.00	\$495.00	\$165.00	\$495.00	\$165.00	\$495.00	\$171.60	\$514.80
159	88600100	DETECTOR LOOP, TYPE I	158.0	FOOT	\$20.00	\$3,160.00	\$15.50	\$2,449.00	\$15.50	\$2,449.00	\$15.50	\$2,449.00	\$16.12	\$2,546.96
160	88700200	LIGHT DETECTOR	3.0	EACH	\$1,400.00	\$4,200.00	\$964.00	\$2,892.00	\$964.00	\$2,892.00	\$964.00	\$2,892.00	\$1,002.56	\$3,007.68
161	88700300	LIGHT DETECTOR AMPLIFIER	1.0	EACH	\$3,500.00	\$3,500.00	\$2,211.00	\$2,211.00	\$2,211.00	\$2,211.00	\$2,211.00	\$2,211.00	\$2,299.44	\$2,299.44
162	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	1.0	EACH	\$60,000.00	\$60,000.00	\$25,400.00	\$25,400.00	\$25,400.00	\$25,400.00	\$25,400.00	\$25,400.00	\$26,416.00	\$26,416.00
163	A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	13.0	EACH	\$500.00	\$6,500.00	\$450.00	\$5,850.00	\$500.00	\$6,500.00	\$500.00	\$6,500.00	\$520.00	\$6,760.00
164	A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	8.0	EACH	\$500.00	\$4,000.00	\$450.00	\$3,600.00	\$500.00	\$4,000.00	\$500.00	\$4,000.00	\$520.00	\$4,160.00
165	A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	5.0	EACH	\$500.00	\$2,500.00	\$450.00	\$2,250.00	\$500.00	\$2,500.00	\$500.00	\$2,500.00	\$520.00	\$2,600.00
166	B0001716	TREE, AMELANCHIER X GRANDIFLORA APPLE, (APPLE SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	5.0	EACH	\$500.00	\$2,500.00	\$450.00	\$2,250.00	\$500.00	\$2,500.00	\$500.00	\$2,500.00	\$520.00	\$2,600.00

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60  
**Section:** 12-00138-02-CH  
**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation  
**CPMS Pin:** B-00474C  
**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
167	C2006036	SHRUB, RHUS TYPHINA (STAGHORN SUMAC), 3' HEIGHT, BALLED AND BURLAPPED	7.0	EACH	\$300.00	\$2,100.00	\$85.00	\$595.00	\$85.00	\$595.00	\$85.00	\$595.00	\$88.40	\$618.80
168	C2011736	SHRUB, VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 3' HEIGHT, BALLED AND BURLAPPED	7.0	EACH	\$300.00	\$2,100.00	\$85.00	\$595.00	\$110.00	\$770.00	\$110.00	\$770.00	\$114.40	\$800.80
169	D2001536	EVERGREEN, JUNIPERUS VIRGINIANA (EASTERN RED CEDAR), 3' HEIGHT, BALLED AND BURLAPPED	8.0	EACH	\$500.00	\$4,000.00	\$85.00	\$680.00	\$200.00	\$1,600.00	\$200.00	\$1,600.00	\$208.00	\$1,664.00
170	K0013000	PERENNIAL PLANTS, PRAIRIE TYPE, 2" DIAMETER BY 4" DEEP PLUG	4.0	UNIT	\$500.00	\$2,000.00	\$500.00	\$2,000.00	\$500.00	\$2,000.00	\$500.00	\$2,000.00	\$520.00	\$2,080.00
171	LC200051	REJECTED LOAD TRANSPORTATION	5.0	LOAD	\$450.00	\$2,250.00	\$5.00	\$25.00	\$250.00	\$1,250.00	\$0.01	\$0.05	\$635.90	\$3,179.50
172	LC200100	LANDSCAPE PERFORMANCE GUARANTEE	1.0	L.SUM	\$10,000.00	\$10,000.00	\$7,920.00	\$7,920.00	\$7,750.00	\$7,750.00	\$7,750.00	\$7,750.00	\$18,460.00	\$18,460.00
173	LC200501	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	11,400.0	UNIT	\$1.00	\$11,400.00	\$1.00	\$11,400.00	\$1.00	\$11,400.00	\$1.00	\$11,400.00	\$1.00	\$11,400.00
174	LC200505	EROSION CONTROL MAT	500.0	SQ YD	\$2.00	\$1,000.00	\$6.00	\$3,000.00	\$1.00	\$500.00	\$1.00	\$500.00	\$1.04	\$520.00
175	LC500229	GRATED CULVERT END SECTIONS, 30" DIAMETER	1.0	EACH	\$1,200.00	\$1,200.00	\$2,500.00	\$2,500.00	\$3,154.00	\$3,154.00	\$5,000.00	\$5,000.00	\$2,162.12	\$2,162.12
176	LC600200	INSTALL SURVEY MONUMENTS	2.0	EACH	\$500.00	\$1,000.00	\$800.00	\$1,600.00	\$900.00	\$1,800.00	\$800.00	\$1,600.00	\$836.64	\$1,673.28
177	LC780031	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 4"	2,975.0	FOOT	\$1.15	\$3,421.25	\$4.00	\$11,900.00	\$4.00	\$11,900.00	\$2.50	\$7,437.50	\$4.16	\$12,376.00
178	LC780033	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 6"	352.0	FOOT	\$2.00	\$704.00	\$6.00	\$2,112.00	\$6.00	\$2,112.00	\$3.60	\$1,267.20	\$6.24	\$2,196.48
179	LC800862	WIRELESS TRANSMISSION SYSTEM POINT TO POINT	2.0	EACH	\$1,000.00	\$2,000.00	\$5,790.00	\$11,580.00	\$5,790.00	\$11,580.00	\$5,790.00	\$11,580.00	\$6,021.60	\$12,043.20
180	X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	791.0	FOOT	\$1.25	\$988.75	\$1.00	\$791.00	\$1.00	\$791.00	\$1.00	\$791.00	\$1.04	\$822.64

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
181	X0326309	RELOCATE EXISTING REMOTE-CONTROLLED VIDEO SYSTEM (SPECIAL)	1.0	EACH	\$2,000.00	\$2,000.00	\$1,680.00	\$1,680.00	\$1,680.00	\$1,680.00	\$1,680.00	\$1,680.00	\$1,747.20	\$1,747.20
182	X0327211	RELOCATE SWITCH	1.0	EACH	\$1,000.00	\$1,000.00	\$485.00	\$485.00	\$485.00	\$485.00	\$485.00	\$485.00	\$504.40	\$504.40
183	X0426200	DEWATERING	1.0	L SUM	\$15,000.00	\$15,000.00	\$1.00	\$1.00	\$2,500.00	\$2,500.00	\$0.01	\$0.01	\$33,000.00	\$33,000.00
184	X0488100	REMOVING EXISTING SEPTIC TANK	1.0	EACH	\$5,000.00	\$5,000.00	\$3,300.00	\$3,300.00	\$850.00	\$850.00	\$1,000.00	\$1,000.00	\$5,200.00	\$5,200.00
185	1200108	INLET BOX, SPECIAL	1.0	EACH	\$6,000.00	\$6,000.00	\$15,000.00	\$15,000.00	\$15,500.00	\$15,500.00	\$15,000.00	\$15,000.00	\$22,042.03	\$22,042.03
186	X1400102	OUTDOOR RATED NETWORK CABLE	187.0	FOOT	\$3.00	\$561.00	\$2.30	\$430.10	\$2.30	\$430.10	\$2.30	\$430.10	\$2.39	\$446.93
187	X1400107	FULL-ACTUATED CONTROLLER AND TYPE SUPER P CABINET	1.0	EACH	\$25,000.00	\$25,000.00	\$14,446.00	\$14,446.00	\$14,446.00	\$14,446.00	\$14,446.00	\$14,446.00	\$15,023.84	\$15,023.84
188	X1400150	SERVICE INSTALLATION, GROUND MOUNTED, METERED	1.0	EACH	\$2,500.00	\$2,500.00	\$2,375.00	\$2,375.00	\$2,375.00	\$2,375.00	\$2,375.00	\$2,375.00	\$2,470.00	\$2,470.00
189	X1400201	RADAR VEHICLE DETECTION SYSTEM, SINGLE APPROACH, STOP BAR	1.0	EACH	\$8,000.00	\$8,000.00	\$7,935.00	\$7,935.00	\$7,935.00	\$7,935.00	\$7,935.00	\$7,935.00	\$8,252.40	\$8,252.40
190	X1400216	LAYER II (DATALINK) SWITCH	1.0	EACH	\$5,000.00	\$5,000.00	\$5,127.00	\$5,127.00	\$5,127.00	\$5,127.00	\$5,127.00	\$5,127.00	\$5,332.08	\$5,332.08
191	X1400217	TERMINATE FIBER IN CABINET	24.0	EACH	\$200.00	\$4,800.00	\$207.00	\$4,968.00	\$207.00	\$4,968.00	\$207.00	\$4,968.00	\$215.28	\$5,166.72
192	X1400219	SPLICE FIBER IN CABINET	12.0	EACH	\$150.00	\$1,800.00	\$201.00	\$2,412.00	\$201.00	\$2,412.00	\$201.00	\$2,412.00	\$209.04	\$2,508.48
193	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	1,111.0	CU YD	\$55.00	\$61,105.00	\$68.00	\$75,548.00	\$79.20	\$87,991.20	\$70.00	\$77,770.00	\$47.59	\$52,872.49
194	X2130010	EXPLORATION TRENCH, SPECIAL	150.0	FOOT	\$25.00	\$3,750.00	\$20.00	\$3,000.00	\$20.00	\$3,000.00	\$10.00	\$1,500.00	\$44.92	\$6,738.00
195	X2501800	SEEDING, CLASS 4 (MODIFIED)	0.3	ACRE	\$2,000.00	\$500.00	\$5,160.00	\$1,290.00	\$4,250.00	\$1,062.50	\$4,250.00	\$1,062.50	\$4,420.00	\$1,105.00
196	X2502014	SEEDING, CLASS 4A (MODIFIED)	0.3	ACRE	\$2,000.00	\$500.00	\$5,385.00	\$1,346.25	\$5,200.00	\$1,300.00	\$5,200.00	\$1,300.00	\$5,408.00	\$1,352.00
197	X2502024	SEEDING, CLASS 4B (MODIFIED)	0.3	ACRE	\$2,000.00	\$500.00	\$3,890.00	\$972.50	\$6,000.00	\$1,500.00	\$6,000.00	\$1,500.00	\$6,240.00	\$1,560.00
198	X2511630	EROSION CONTROL BLANKET (SPECIAL)	100.0	SQ YD	\$1.00	\$100.00	\$2.50	\$250.00	\$5.00	\$500.00	\$5.00	\$500.00	\$5.20	\$520.00
199	X2800500	INLET PROTECTION, SPECIAL	12.0	EACH	\$150.00	\$1,800.00	\$300.00	\$3,600.00	\$125.00	\$1,500.00	\$125.00	\$1,500.00	\$130.00	\$1,560.00

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60  
**Section:** 12-00138-02-CH  
**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation  
**CPMS Pin:** B-00474C  
**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
200	X3400004	RETAINING WALL REMOVAL	27.0	FOOT	\$30.00	\$810.00	\$45.00	\$1,215.00	\$25.00	\$675.00	\$10.00	\$270.00	\$51.36	\$1,386.72
201	X6050700	REMOVE INLET BOX	1.0	EACH	\$1,440.00	\$1,440.00	\$750.00	\$750.00	\$1,000.00	\$1,000.00	\$5,000.00	\$5,000.00	\$2,080.03	\$2,080.03
202	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	8.0	CAL MO	\$3,000.00	\$24,000.00	\$2,400.00	\$19,200.00	\$3,000.00	\$24,000.00	\$3,000.00	\$24,000.00	\$3,718.77	\$29,750.16
203	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1.0	LSUM	\$90,000.00	\$90,000.00	\$75,000.00	\$75,000.00	\$24,000.00	\$24,000.00	\$126,000.00	\$126,000.00	\$151,390.11	\$151,390.11
204	X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	2,184.0	SQ FT	\$0.50	\$1,092.00	\$0.40	\$873.60	\$0.40	\$873.60	\$0.40	\$873.60	\$0.42	\$917.28
205	X7040125	PINNING TEMPORARY CONCRETE BARRIER	450.0	EACH	\$13.00	\$5,850.00	\$19.00	\$8,550.00	\$23.00	\$10,350.00	\$23.00	\$10,350.00	\$20.00	\$9,000.00
206	X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	146.0	SQ FT	\$6.00	\$876.00	\$2.00	\$292.00	\$2.00	\$292.00	\$5.00	\$730.00	\$2.08	\$303.68
207	X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	2,975.0	FOOT	\$0.65	\$1,933.75	\$0.45	\$1,338.75	\$0.45	\$1,338.75	\$0.60	\$1,785.00	\$0.47	\$1,398.25
208	X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	2,357.0	FOOT	\$0.75	\$1,767.75	\$0.55	\$1,296.35	\$0.55	\$1,296.35	\$0.80	\$1,885.60	\$0.57	\$1,343.49
209	X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	352.0	FOOT	\$0.85	\$299.20	\$0.80	\$281.60	\$0.80	\$281.60	\$1.00	\$352.00	\$0.83	\$292.16
210	X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	84.0	FOOT	\$2.25	\$189.00	\$1.50	\$126.00	\$1.50	\$126.00	\$2.00	\$168.00	\$1.56	\$131.04
211	X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	52.0	FOOT	\$4.00	\$208.00	\$2.00	\$104.00	\$2.00	\$104.00	\$4.00	\$208.00	\$2.08	\$108.16
212	X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	1.0	EACH	\$8,000.00	\$8,000.00	\$4,393.00	\$4,393.00	\$4,393.00	\$4,393.00	\$4,393.00	\$4,393.00	\$4,568.72	\$4,568.72
213	X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	1,755.0	FOOT	\$4.00	\$7,020.00	\$3.30	\$5,791.50	\$3.30	\$5,791.50	\$3.30	\$5,791.50	\$3.43	\$6,019.65
214	XX000856	MAILBOX REMOVAL AND RELOCATION	2.0	EACH	\$300.00	\$600.00	\$200.00	\$400.00	\$150.00	\$300.00	\$100.00	\$200.00	\$852.07	\$1,704.14

## Return Bid Tabulation

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Berger Excavating Contractors		Campanella & Sons, Inc.		Lake County Grading Company		Martam Construction, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
215	XX003668	PRECONSTRUCTION VIDEO TAPING	1.0	LSUM	\$3,500.00	\$3,500.00	\$1,800.00	\$1,800.00	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00	\$5,000.00	\$5,000.00
216	XX005940	REMOTE CONTROLLED VIDEO SYSTEM	1.0	EACH	\$7,000.00	\$7,000.00	\$4,925.00	\$4,925.00	\$4,925.00	\$4,925.00	\$4,925.00	\$4,925.00	\$5,122.00	\$5,122.00
217	XX006522	FURNISH WITNESS POST	4.0	EACH	\$100.00	\$400.00	\$250.00	\$1,000.00	\$200.00	\$800.00	\$55.00	\$220.00	\$1,330.99	\$5,323.96
218	XX006658	FLOCCULATION LOGS	100.0	EACH	\$50.00	\$5,000.00	\$0.50	\$50.00	\$1.00	\$100.00	\$0.01	\$1.00	\$1.04	\$104.00
219	XX006659	FLOCCULATION POWDER	20.0	POUND	\$35.00	\$700.00	\$2.00	\$40.00	\$1.00	\$20.00	\$0.01	\$0.20	\$1.04	\$20.80
220	XX008865	PERMEABLE PLASTIC BERM	96.0	FOOT	\$20.00	\$1,920.00	\$12.00	\$1,152.00	\$15.00	\$1,440.00	\$15.00	\$1,440.00	\$15.60	\$1,497.60
221	XX009142	PAVEMENT MARKING REMOVAL (SPECIAL)	567.0	SQ FT	\$1.00	\$567.00	\$0.60	\$340.20	\$0.60	\$340.20	\$0.60	\$340.20	\$0.31	\$175.77
222	XX206400	MAILBOX POST	2.0	EACH	\$150.00	\$300.00	\$200.00	\$400.00	\$150.00	\$300.00	\$200.00	\$400.00	\$200.00	\$400.00
223	Z0007601	BUILDING REMOVAL NO. 1	1.0	L SUM	\$30,000.00	\$30,000.00	\$14,500.00	\$14,500.00	\$21,000.00	\$21,000.00	\$75,956.13	\$75,956.13	\$20,696.00	\$20,696.00
224	Z0013797	STABILIZED CONSTRUCTION ENTRANCE	188.0	SQ YD	\$45.00	\$8,460.00	\$32.00	\$6,016.00	\$25.50	\$4,794.00	\$30.00	\$5,640.00	\$20.87	\$3,923.56
225	Z0013798	CONSTRUCTION LAYOUT	1.0	L SUM	\$36,000.00	\$36,000.00	\$97,000.00	\$97,000.00	\$16,500.00	\$16,500.00	\$37,500.00	\$37,500.00	\$31,200.00	\$31,200.00
226	Z0019600	DUST CONTROL WATERING	20.0	UNIT	\$100.00	\$2,000.00	\$1.00	\$20.00	\$50.00	\$1,000.00	\$100.00	\$2,000.00	\$100.00	\$2,000.00
227	Z0022800	FENCE REMOVAL	1,539.0	FOOT	\$5.00	\$7,695.00	\$4.00	\$6,156.00	\$4.40	\$6,771.60	\$6.50	\$10,003.50	\$9.44	\$14,528.16
228	Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	1.0	EACH	\$10,000.00	\$10,000.00	\$2,355.00	\$2,355.00	\$2,355.00	\$2,355.00	\$2,355.00	\$2,355.00	\$2,449.20	\$2,449.20
229	Z0033700	LONGITUDINAL JOINT SEALANT	9,030.0	FOOT	\$2.25	\$20,317.50	\$2.80	\$25,284.00	\$2.80	\$25,284.00	\$2.80	\$25,284.00	\$2.93	\$26,457.90
230	Z0055905	TEMPORARY CONSTRUCTION FENCE	2,882.0	FOOT	\$4.00	\$11,528.00	\$3.00	\$8,646.00	\$5.05	\$14,554.10	\$3.50	\$10,087.00	\$4.42	\$12,738.44
231	Z0062450	SAWING PAVEMENT (FULL DEPTH)	4,166.0	FOOT	\$5.00	\$20,830.00	\$2.85	\$11,873.10	\$2.25	\$9,373.50	\$2.00	\$8,332.00	\$2.25	\$9,373.50
232	Z0062456	TEMPORARY PAVEMENT	446.0	SQ YD	\$60.00	\$26,760.00	\$46.00	\$20,516.00	\$46.00	\$20,516.00	\$46.00	\$20,516.00	\$81.00	\$36,126.00
233	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	4.0	EACH	\$2,000.00	\$8,000.00	\$485.00	\$1,940.00	\$485.00	\$1,940.00	\$485.00	\$1,940.00	\$504.40	\$2,017.60
<b>Bid Total</b>					<b>\$2,895,512.95</b>		<b>\$2,133,208.86</b>		<b>\$2,265,594.10</b>		<b>\$2,233,445.50</b>		<b>\$2,992,779.84</b>	

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	626.0	UNIT	\$40.00	\$25,040.00	\$9.00	\$28.08	\$13.77
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	488.0	UNIT	\$40.00	\$19,520.00	\$11.00	\$40.56	\$18.39
3	20101100	TREE TRUNK PROTECTION	21.0	EACH	\$130.00	\$2,730.00	\$180.00	\$182.00	\$180.50
4	20101200	TREE ROOT PRUNING	21.0	EACH	\$100.00	\$2,100.00	\$90.00	\$156.00	\$106.50
5	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	14.0	EACH	\$75.00	\$1,050.00	\$40.00	\$130.00	\$62.50
6	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	7.0	EACH	\$100.00	\$700.00	\$120.00	\$182.00	\$135.50
7	20200100	EARTH EXCAVATION	12,327.0	CU YD	\$22.00	\$271,194.00	\$0.01	\$27.00	\$9.83
8	20400800	FURNISHED EXCAVATION	100.0	CU YD	\$50.00	\$5,000.00	\$0.01	\$87.60	\$48.13
9	20800150	TRENCH BACKFILL	340.0	CU YD	\$45.00	\$15,300.00	\$20.00	\$67.59	\$41.15
10	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	10,422.0	SQ YD	\$4.00	\$41,688.00	\$1.50	\$2.10	\$1.80
11	21101615	TOPSOIL FURNISH AND PLACE, 4"	14,365.0	SQ YD	\$4.50	\$64,642.50	\$0.01	\$4.16	\$2.34
12	21101805	COMPOST FURNISH AND PLACE, 2"	7,026.0	SQ YD	\$3.00	\$21,078.00	\$2.85	\$4.16	\$3.75
13	25000210	SEEDING, CLASS 2A	3.0	ACRE	\$2,500.00	\$7,500.00	\$2,960.00	\$3,120.00	\$3,020.00



## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
14	25000400	NITROGEN FERTILIZER NUTRIENT	293.0	POUND	\$3.00	\$879.00	\$1.00	\$1.10	\$1.04
15	25000600	POTASSIUM FERTILIZER NUTRIENT	293.0	POUND	\$3.00	\$879.00	\$1.00	\$1.10	\$1.04
16	25100630	EROSION CONTROL BLANKET	14,223.0	SQ YD	\$1.00	\$14,223.00	\$1.10	\$1.72	\$1.53
17	25200200	SUPPLEMENTAL WATERING	28.0	UNIT	\$150.00	\$4,200.00	\$0.10	\$40.00	\$10.08
18	28000250	TEMPORARY EROSION CONTROL SEEDING	384.0	POUND	\$5.00	\$1,920.00	\$0.10	\$5.00	\$1.33
19	28000305	TEMPORARY DITCH CHECKS	238.0	FOOT	\$20.00	\$4,760.00	\$12.00	\$15.00	\$12.87
20	28000400	PERIMETER EROSION BARRIER	2,342.0	FOOT	\$3.00	\$7,026.00	\$3.00	\$3.12	\$3.03
21	28000510	INLET FILTERS	5.0	EACH	\$150.00	\$750.00	\$140.00	\$250.00	\$168.90
22	28001100	TEMPORARY EROSION CONTROL BLANKET	18,541.0	SQ YD	\$0.60	\$11,124.60	\$0.50	\$1.10	\$0.66
23	28100105	STONE RIPRAP, CLASS A3	46.0	SQ YD	\$40.00	\$1,840.00	\$57.45	\$100.00	\$84.99
24	28200200	FILTER FABRIC	58.0	SQ YD	\$8.00	\$464.00	\$2.00	\$7.35	\$4.34
25	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	10,390.0	SQ YD	\$14.00	\$145,460.00	\$14.00	\$19.03	\$16.33
26	35101800	AGGREGATE BASE COURSE, TYPE B 6"	231.0	SQ YD	\$9.00	\$2,079.00	\$8.62	\$12.74	\$10.50
27	35102000	AGGREGATE BASE COURSE, TYPE B 8"	459.0	SQ YD	\$10.00	\$4,590.00	\$11.94	\$14.75	\$12.74

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extn. Price			
28	35501315	HOT-MIX ASPHALT BASE COURSE, 7 3/4"	2,469.0	SQ YD	\$50.00	\$123,450.00	\$30.70	\$32.11	\$31.05
29	40201000	AGGREGATE FOR TEMPORARY ACCESS	218.0	TON	\$40.00	\$8,720.00	\$0.01	\$25.55	\$17.42
30	40600290	BITUMINOUS MATERIALS (TACK COAT)	8,973.0	POUND	\$1.00	\$8,973.00	\$0.01	\$0.01	\$0.01
31	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	10.0	TON	\$300.00	\$3,000.00	\$75.00	\$78.44	\$75.86
32	40600525	LEVELING BINDER (HAND METHOD), N50	5.0	TON	\$120.00	\$600.00	\$75.00	\$78.43	\$75.86
33	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	68.0	SQ YD	\$20.00	\$1,360.00	\$10.00	\$10.46	\$10.12
34	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	1,464.0	TON	\$80.00	\$117,120.00	\$69.00	\$72.16	\$69.79
35	40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	827.0	TON	\$100.00	\$82,700.00	\$84.20	\$88.06	\$85.17
36	40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	514.0	TON	\$100.00	\$51,400.00	\$82.10	\$85.86	\$83.04
37	40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	654.0	TON	\$100.00	\$65,400.00	\$80.00	\$83.66	\$80.92
38	42001300	PROTECTIVE COAT	569.0	SQ YD	\$1.50	\$853.50	\$0.01	\$5.00	\$3.04
39	44000100	PAVEMENT REMOVAL	2,714.0	SQ YD	\$15.00	\$40,710.00	\$5.50	\$11.32	\$8.14
40	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	1,760.0	SQ YD	\$4.50	\$7,920.00	\$4.70	\$4.92	\$4.76

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
41	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	4,421.0	SQ YD	\$4.50	\$19,894.50	\$3.00	\$3.14	\$3.04
42	44000200	DRIVEWAY PAVEMENT REMOVAL	662.0	SQ YD	\$13.00	\$8,606.00	\$3.06	\$11.04	\$6.09
43	44004250	PAVED SHOULDER REMOVAL	1,001.0	SQ YD	\$10.00	\$10,010.00	\$4.00	\$10.37	\$6.97
44	44201773	CLASS D PATCHES, TYPE I, 11 INCH	10.0	SQ YD	\$90.00	\$900.00	\$40.00	\$56.56	\$44.14
45	44201777	CLASS D PATCHES, TYPE II, 11 INCH	31.0	SQ YD	\$90.00	\$2,790.00	\$40.00	\$56.47	\$44.12
46	44201781	CLASS D PATCHES, TYPE III, 11 INCH	68.0	SQ YD	\$90.00	\$6,120.00	\$40.00	\$56.42	\$44.11
47	44201783	CLASS D PATCHES, TYPE IV, 11 INCH	68.0	SQ YD	\$90.00	\$6,120.00	\$40.00	\$56.42	\$44.11
48	48101200	AGGREGATE SHOULDERS, TYPE B	213.0	TON	\$45.00	\$9,585.00	\$31.00	\$59.46	\$44.52
49	48203100	HOT-MIX ASPHALT SHOULDERS	1,841.0	TON	\$85.00	\$156,485.00	\$64.60	\$67.56	\$65.34
50	50104400	CONCRETE HEADWALL REMOVAL	2.0	EACH	\$500.00	\$1,000.00	\$346.68	\$2,850.00	\$1,211.67
51	54002020	EXPANSION BOLTS 3/4 INCH	8.0	EACH	\$30.00	\$240.00	\$0.01	\$415.00	\$147.12
52	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	2.0	EACH	\$400.00	\$800.00	\$721.76	\$2,000.00	\$1,464.19
53	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	12.0	EACH	\$450.00	\$5,400.00	\$752.50	\$2,000.00	\$1,548.13
54	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	1.0	EACH	\$500.00	\$500.00	\$810.64	\$2,000.00	\$1,615.16

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
55	54248510	CONCRETE COLLAR	0.3	CU YD	\$763.00	\$228.90	\$3,202.97	\$26,500.00	\$10,113.24
56	54260515	SLOPED METAL END SECTION, STANDARD 542411, 15", 1:6	2.0	EACH	\$150.00	\$300.00	\$500.00	\$1,878.49	\$1,123.37
57	54260521	SLOPED METAL END SECTION, STANDARD 542411, 21", 1:6	3.0	EACH	\$200.00	\$600.00	\$1,100.00	\$1,878.50	\$1,475.88
58	542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	27.0	FOOT	\$50.00	\$1,350.00	\$40.00	\$91.46	\$60.05
59	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	15.0	FOOT	\$75.00	\$1,125.00	\$42.50	\$88.13	\$62.16
60	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	145.0	FOOT	\$80.00	\$11,600.00	\$45.80	\$77.98	\$57.36
61	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	80.0	FOOT	\$80.00	\$6,400.00	\$42.00	\$74.65	\$54.44
62	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	705.0	FOOT	\$80.00	\$56,400.00	\$46.00	\$83.82	\$57.08
63	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	21.0	FOOT	\$90.00	\$1,890.00	\$117.81	\$165.00	\$141.20
64	55100100	STORM SEWER REMOVAL 4"	22.0	FOOT	\$10.00	\$220.00	\$11.00	\$15.00	\$12.45
65	55100500	STORM SEWER REMOVAL 12"	849.0	FOOT	\$12.00	\$10,188.00	\$11.75	\$15.50	\$14.31
66	55100700	STORM SEWER REMOVAL 15"	307.0	FOOT	\$15.00	\$4,605.00	\$11.75	\$20.00	\$15.94
67	55100900	STORM SEWER REMOVAL 18"	165.0	FOOT	\$18.00	\$2,970.00	\$11.74	\$20.00	\$15.94
68	60100905	PIPE DRAINS 4"	100.0	FOOT	\$30.00	\$3,000.00	\$0.01	\$28.58	\$17.15
69	60100915	PIPE DRAINS 6"	100.0	FOOT	\$35.00	\$3,500.00	\$0.01	\$28.58	\$18.52

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
70	60108104	PIPE UNDERDRAINS, TYPE 1, 4"	5,277.0	FOOT	\$15.00	\$79,155.00	\$3.25	\$28.58	\$9.93
71	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	1.0	EACH	\$3,500.00	\$3,500.00	\$2,400.00	\$3,200.00	\$2,784.75
72	60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	1.0	EACH	\$4,500.00	\$4,500.00	\$3,450.00	\$4,200.00	\$3,774.10
73	60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	1.0	EACH	\$2,000.00	\$2,000.00	\$1,610.00	\$2,950.00	\$2,280.24
74	60207000	CATCH BASINS, TYPE C, TYPE 8 GRATE	1.0	EACH	\$2,000.00	\$2,000.00	\$1,225.00	\$2,600.00	\$1,771.32
75	60207005	CATCH BASINS, TYPE C, TYPE 1 FRAME, CLOSED LID	9.0	EACH	\$2,000.00	\$18,000.00	\$1,590.00	\$2,700.00	\$1,968.98
76	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	3.0	EACH	\$2,000.00	\$6,000.00	\$1,550.00	\$2,700.00	\$1,970.16
77	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	3.0	EACH	\$3,500.00	\$10,500.00	\$2,125.00	\$3,200.00	\$2,679.43
78	60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	3.0	EACH	\$4,100.00	\$12,300.00	\$3,600.00	\$4,400.00	\$4,038.75
79	60257900	MANHOLES TO BE RECONSTRUCTED	1.0	EACH	\$1,500.00	\$1,500.00	\$985.00	\$2,150.00	\$1,380.42
80	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	1.0	EACH	\$400.00	\$400.00	\$260.00	\$820.00	\$555.91
81	60500040	REMOVING MANHOLES	2.0	EACH	\$500.00	\$1,000.00	\$500.00	\$1,040.02	\$735.01
82	60500050	REMOVING CATCH BASINS	1.0	EACH	\$500.00	\$500.00	\$500.00	\$1,040.06	\$735.02

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
83	60500060	REMOVING INLETS	2.0	EACH	\$250.00	\$500.00	\$300.00	\$520.03	\$411.26
84	60600095	CLASS SI CONCRETE (OUTLET)	3.0	CU YD	\$750.00	\$2,250.00	\$425.00	\$927.00	\$720.50
85	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	1,123.0	FOOT	\$28.00	\$31,444.00	\$23.50	\$29.56	\$26.33
86	60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	603.0	FOOT	\$28.00	\$16,884.00	\$23.50	\$31.60	\$27.04
87	61101013	STORM SEWERS PROTECTED, CLASS A, 12"	370.0	FOOT	\$75.00	\$27,750.00	\$37.00	\$88.13	\$54.16
88	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	796.0	FOOT	\$30.00	\$23,880.00	\$33.50	\$36.40	\$34.98
89	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	1.0	EACH	\$3,000.00	\$3,000.00	\$3,500.00	\$3,952.00	\$3,763.00
90	63200310	GUARDRAIL REMOVAL	714.0	FOOT	\$10.00	\$7,140.00	\$5.00	\$6.76	\$6.19
91	66900200	NON-SPECIAL WASTE DISPOSAL	300.0	CU YD	\$75.00	\$22,500.00	\$0.01	\$83.00	\$59.50
92	66900530	SOIL DISPOSAL ANALYSIS	3.0	EACH	\$1,800.00	\$5,400.00	\$0.01	\$1,500.00	\$1,072.40
93	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	1.0	L SUM	\$3,500.00	\$3,500.00	\$0.01	\$3,500.00	\$2,400.00
94	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	1.0	L SUM	\$3,000.00	\$3,000.00	\$0.01	\$3,500.00	\$2,244.00
95	66901006	REGULATED SUBSTANCES MONITORING	5.0	CAL DA	\$900.00	\$4,500.00	\$0.01	\$1,000.00	\$715.80

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
96	67100100	MOBILIZATION	1.0	LSUM	\$170,000.00	\$170,000.00	\$84,500.00	\$178,686.65	\$131,046.66
97	70106800	CHANGEABLE MESSAGE SIGN	18.0	CAL M	\$800.00	\$14,400.00	\$700.00	\$728.00	\$707.00
98	70300100	SHORT TERM PAVEMENT MARKING	1,119.0	FOOT	\$0.75	\$839.25	\$0.30	\$0.31	\$0.30
99	70300150	SHORT TERM PAVEMENT MARKING REMOVAL	374.0	SQ FT	\$1.00	\$374.00	\$1.00	\$4.00	\$1.75
100	70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	219.0	SQ FT	\$0.25	\$54.75	\$1.00	\$1.56	\$1.14
101	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	25,431.0	FOOT	\$0.25	\$6,357.75	\$0.20	\$0.31	\$0.23
102	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	2,357.0	FOOT	\$0.30	\$707.10	\$0.24	\$0.42	\$0.29
103	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	731.0	FOOT	\$0.35	\$255.85	\$0.28	\$0.52	\$0.34
104	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	347.0	FOOT	\$0.65	\$225.55	\$0.65	\$0.73	\$0.67
105	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	121.0	FOOT	\$1.00	\$121.00	\$1.00	\$1.56	\$1.14
106	70300904	PAVEMENT MARKING TAPE, TYPE IV, 4"	1,699.0	FOOT	\$1.25	\$2,123.75	\$0.80	\$1.30	\$0.98
107	70400100	TEMPORARY CONCRETE BARRIER	1,464.0	FOOT	\$20.00	\$29,280.00	\$18.00	\$21.00	\$20.00

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
108	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	1,448.0	FOOT	\$8.00	\$11,584.00	\$3.25	\$8.00	\$4.94
109	70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	6.0	EACH	\$4,500.00	\$27,000.00	\$4,500.00	\$6,864.00	\$6,141.00
110	70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	5.0	EACH	\$500.00	\$2,500.00	\$2,000.00	\$2,444.00	\$2,286.00
111	72000100	SIGN PANEL - TYPE 1	30.0	SQ FT	\$25.00	\$750.00	\$26.17	\$57.00	\$42.67
112	72000200	SIGN PANEL - TYPE 2	26.0	SQ FT	\$30.00	\$780.00	\$57.10	\$62.40	\$58.65
113	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	7.0	EACH	\$70.00	\$490.00	\$40.00	\$72.80	\$48.20
114	72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	2.0	EACH	\$80.00	\$160.00	\$60.00	\$72.80	\$63.20
115	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	5.0	EACH	\$100.00	\$500.00	\$72.80	\$100.00	\$93.20
116	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	2.0	EACH	\$120.00	\$240.00	\$72.80	\$100.00	\$93.20
117	72800100	TELESCOPING STEEL SIGN SUPPORT	49.0	FOOT	\$15.00	\$735.00	\$9.50	\$18.72	\$11.81
118	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	219.0	SQ FT	\$5.00	\$1,095.00	\$4.00	\$4.16	\$4.04



## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
119	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	9,367.0	FOOT	\$0.65	\$6,088.55	\$0.55	\$0.70	\$0.59
120	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	2,357.0	FOOT	\$0.75	\$1,767.75	\$0.60	\$0.90	\$0.68
121	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	379.0	FOOT	\$1.10	\$416.90	\$0.75	\$1.00	\$0.82
122	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	347.0	FOOT	\$2.25	\$780.75	\$1.00	\$2.00	\$1.26
123	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	121.0	FOOT	\$5.00	\$605.00	\$4.00	\$4.16	\$4.04
124	78100100	RAISED REFLECTIVE PAVEMENT MARKER	80.0	EACH	\$33.00	\$2,640.00	\$50.00	\$60.00	\$53.00
125	78200005	GUARDRAIL REFLECTORS, TYPE A	7.0	EACH	\$50.00	\$350.00	\$10.00	\$11.00	\$10.35
126	78200011	BARRIER WALL REFLECTORS, TYPE C	44.0	EACH	\$10.00	\$440.00	\$6.00	\$15.60	\$8.40
127	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	44.0	EACH	\$10.00	\$440.00	\$15.00	\$25.88	\$17.72
128	78300202	PAVEMENT MARKING REMOVAL – WATER BLASTING	1,365.0	SQ FT	\$1.00	\$1,365.00	\$2.35	\$3.12	\$2.54
129	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	1,824.0	FOOT	\$20.00	\$36,480.00	\$19.50	\$20.28	\$19.70

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
130	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	424.0	FOOT	\$30.00	\$12,720.00	\$37.40	\$38.90	\$37.78
131	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	323.0	FOOT	\$40.00	\$12,920.00	\$57.00	\$59.28	\$57.57
132	81400100	HANDHOLE	1.0	EACH	\$1,500.00	\$1,500.00	\$1,401.00	\$1,457.04	\$1,415.01
133	81400200	HEAVY-DUTY HANDHOLE	7.0	EACH	\$2,000.00	\$14,000.00	\$1,792.00	\$1,863.68	\$1,809.92
134	81400300	DOUBLE HANDHOLE	1.0	EACH	\$2,800.00	\$2,800.00	\$2,480.00	\$2,579.20	\$2,504.80
135	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	1.0	EACH	\$2,000.00	\$2,000.00	\$420.00	\$436.80	\$424.20
136	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	1,732.0	FOOT	\$1.40	\$2,424.80	\$0.70	\$0.73	\$0.71
137	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	484.0	FOOT	\$1.40	\$677.60	\$1.20	\$1.25	\$1.21
138	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	1,380.0	FOOT	\$1.50	\$2,070.00	\$1.40	\$1.46	\$1.42
139	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	1,267.0	FOOT	\$1.60	\$2,027.20	\$1.70	\$1.77	\$1.72
140	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	1,019.0	FOOT	\$1.80	\$1,834.20	\$1.00	\$1.04	\$1.01
141	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	275.0	FOOT	\$3.50	\$962.50	\$3.20	\$3.33	\$3.23

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extn. Price			
142	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	1,161.0	FOOT	\$2.50	\$2,902.50	\$1.70	\$1.77	\$1.72
143	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	3.0	EACH	\$1,600.00	\$4,800.00	\$1,102.00	\$1,146.08	\$1,113.02
144	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	1.0	EACH	\$1,800.00	\$1,800.00	\$1,258.00	\$1,308.32	\$1,270.58
145	87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	1.0	EACH	\$11,000.00	\$11,000.00	\$8,870.00	\$9,224.80	\$8,958.70
146	87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	1.0	EACH	\$15,000.00	\$15,000.00	\$14,452.00	\$15,030.08	\$14,596.52
147	87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 32 FT.	1.0	EACH	\$16,000.00	\$16,000.00	\$14,683.00	\$15,270.32	\$14,829.83
148	87800100	CONCRETE FOUNDATION, TYPE A	21.0	FOOT	\$250.00	\$5,250.00	\$240.00	\$249.60	\$242.40
149	87800150	CONCRETE FOUNDATION, TYPE C	4.0	FOOT	\$600.00	\$2,400.00	\$662.00	\$688.48	\$668.62
150	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	10.0	FOOT	\$200.00	\$2,000.00	\$204.00	\$212.16	\$206.04
151	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	24.0	FOOT	\$250.00	\$6,000.00	\$215.00	\$223.60	\$217.15
152	87900200	DRILL EXISTING HANDHOLE	1.0	EACH	\$300.00	\$300.00	\$269.00	\$279.76	\$271.69

### Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
153	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	4.0	EACH	\$850.00	\$3,400.00	\$643.00	\$668.72	\$649.43
154	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	5.0	EACH	\$800.00	\$4,000.00	\$592.00	\$615.68	\$597.92
155	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	2.0	EACH	\$1,100.00	\$2,200.00	\$877.00	\$912.08	\$885.77
156	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	2.0	EACH	\$1,200.00	\$2,400.00	\$926.00	\$963.04	\$935.26
157	88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	6.0	EACH	\$200.00	\$1,200.00	\$254.00	\$264.16	\$256.54
158	88500100	INDUCTIVE LOOP DETECTOR	3.0	EACH	\$200.00	\$600.00	\$165.00	\$171.60	\$166.65
159	88600100	DETECTOR LOOP, TYPE I	158.0	FOOT	\$20.00	\$3,160.00	\$15.50	\$16.12	\$15.66
160	88700200	LIGHT DETECTOR	3.0	EACH	\$1,400.00	\$4,200.00	\$964.00	\$1,002.56	\$973.64
161	88700300	LIGHT DETECTOR AMPLIFIER	1.0	EACH	\$3,500.00	\$3,500.00	\$2,211.00	\$2,299.44	\$2,233.11
162	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	1.0	EACH	\$60,000.00	\$60,000.00	\$25,400.00	\$26,416.00	\$25,654.00
163	A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	13.0	EACH	\$500.00	\$6,500.00	\$450.00	\$520.00	\$492.50

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
164	A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	8.0	EACH	\$500.00	\$4,000.00	\$450.00	\$520.00	\$492.50
165	A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	5.0	EACH	\$500.00	\$2,500.00	\$450.00	\$520.00	\$492.50
166	B0001716	TREE, AMELANCHIER X GRANDIFLORA APPLE, (APPLE SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	5.0	EACH	\$500.00	\$2,500.00	\$450.00	\$520.00	\$492.50
167	C2006036	SHRUB, RHUS TYPHINA (STAGHORN SUMAC), 3' HEIGHT, BALLED AND BURLAPPED	7.0	EACH	\$300.00	\$2,100.00	\$85.00	\$88.40	\$85.85
168	C2011736	SHRUB, VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 3' HEIGHT, BALLED AND BURLAPPED	7.0	EACH	\$300.00	\$2,100.00	\$85.00	\$114.40	\$104.85
169	D2001536	EVERGREEN, JUNIPERUS VIRGINIANA (EASTERN RED CEDAR), 3' HEIGHT, BALLED AND BURLAPPED	8.0	EACH	\$500.00	\$4,000.00	\$85.00	\$208.00	\$173.25
170	K0013000	PERENNIAL PLANTS, PRAIRIE TYPE, 2" DIAMETER BY 4" DEEP PLUG	4.0	UNIT	\$500.00	\$2,000.00	\$500.00	\$520.00	\$505.00
171	LC200051	REJECTED LOAD TRANSPORTATION	5.0	LOAD	\$450.00	\$2,250.00	\$0.01	\$635.90	\$222.73

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
172	LC200100	LANDSCAPE PERFORMANCE GUARANTEE	1.0	L.SUM	\$10,000.00	\$10,000.00	\$7,750.00	\$18,460.00	\$10,470.00
173	LC200501	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	11,400.0	UNIT	\$1.00	\$11,400.00	\$1.00	\$1.00	\$1.00
174	LC200505	EROSION CONTROL MAT	500.0	SQ YD	\$2.00	\$1,000.00	\$1.00	\$6.00	\$2.26
175	LC500229	GRATED CULVERT END SECTIONS, 30" DIAMETER	1.0	EACH	\$1,200.00	\$1,200.00	\$2,162.12	\$5,000.00	\$3,204.03
176	LC600200	INSTALL SURVEY MONUMENTS	2.0	EACH	\$500.00	\$1,000.00	\$800.00	\$900.00	\$834.16
177	LC780031	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 4"	2,975.0	FOOT	\$1.15	\$3,421.25	\$2.50	\$4.16	\$3.67
178	LC780033	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 6"	352.0	FOOT	\$2.00	\$704.00	\$3.60	\$6.24	\$5.46
179	LC800862	WIRELESS TRANSMISSION SYSTEM POINT TO POINT	2.0	EACH	\$1,000.00	\$2,000.00	\$5,790.00	\$6,021.60	\$5,847.90
180	X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	791.0	FOOT	\$1.25	\$988.75	\$1.00	\$1.04	\$1.01
181	X0326309	RELOCATE EXISTING REMOTE-CONTROLLED VIDEO SYSTEM (SPECIAL)	1.0	EACH	\$2,000.00	\$2,000.00	\$1,680.00	\$1,747.20	\$1,696.80
182	X0327211	RELOCATE SWITCH	1.0	EACH	\$1,000.00	\$1,000.00	\$485.00	\$504.40	\$489.85

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
183	X0426200	DEWATERING	1.0	L SUM	\$15,000.00	\$15,000.00	\$0.01	\$33,000.00	\$8,875.25
184	X0488100	REMOVING EXISTING SEPTIC TANK	1.0	EACH	\$5,000.00	\$5,000.00	\$850.00	\$5,200.00	\$2,587.50
185	X1200108	INLET BOX, SPECIAL	1.0	EACH	\$6,000.00	\$6,000.00	\$15,000.00	\$22,042.03	\$16,885.51
186	X1400102	OUTDOOR RATED NETWORK CABLE	187.0	FOOT	\$3.00	\$561.00	\$2.30	\$2.39	\$2.32
187	X1400107	FULL-ACTUATED CONTROLLER AND TYPE SUPER P CABINET	1.0	EACH	\$25,000.00	\$25,000.00	\$14,446.00	\$15,023.84	\$14,590.46
188	X1400150	SERVICE INSTALLATION, GROUND MOUNTED, METERED	1.0	EACH	\$2,500.00	\$2,500.00	\$2,375.00	\$2,470.00	\$2,398.75
189	X1400201	RADAR VEHICLE DETECTION SYSTEM, SINGLE APPROACH, STOP BAR	1.0	EACH	\$8,000.00	\$8,000.00	\$7,935.00	\$8,252.40	\$8,014.35
190	X1400216	LAYER II (DATALINK) SWITCH	1.0	EACH	\$5,000.00	\$5,000.00	\$5,127.00	\$5,332.08	\$5,178.27
191	X1400217	TERMINATE FIBER IN CABINET	24.0	EACH	\$200.00	\$4,800.00	\$207.00	\$215.28	\$209.07
192	X1400219	SPLICE FIBER IN CABINET	12.0	EACH	\$150.00	\$1,800.00	\$201.00	\$209.04	\$203.01
193	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	1,111.0	CU YD	\$55.00	\$61,105.00	\$47.59	\$79.20	\$66.20
194	X2130010	EXPLORATION TRENCH, SPECIAL	150.0	FOOT	\$25.00	\$3,750.00	\$10.00	\$44.92	\$23.73
195	X2501800	SEEDING, CLASS 4 (MODIFIED)	0.3	ACRE	\$2,000.00	\$500.00	\$4,250.00	\$5,160.00	\$4,520.00
196	X2502014	SEEDING, CLASS 4A (MODIFIED)	0.3	ACRE	\$2,000.00	\$500.00	\$5,200.00	\$5,408.00	\$5,298.25

### Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
197	X2502024	SEEDING, CLASS 4B (MODIFIED)	0.3	ACRE	\$2,000.00	\$500.00	\$3,890.00	\$6,240.00	\$5,532.50
198	X2511630	EROSION CONTROL BLANKET (SPECIAL)	100.0	SQ YD	\$1.00	\$100.00	\$2.50	\$5.20	\$4.43
199	X2800500	INLET PROTECTION, SPECIAL	12.0	EACH	\$150.00	\$1,800.00	\$125.00	\$300.00	\$170.00
200	X3400004	RETAINING WALL REMOVAL	27.0	FOOT	\$30.00	\$810.00	\$10.00	\$51.36	\$32.84
201	X6050700	REMOVE INLET BOX	1.0	EACH	\$1,440.00	\$1,440.00	\$750.00	\$5,000.00	\$2,207.51
202	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	8.0	CAL MO	\$3,000.00	\$24,000.00	\$2,400.00	\$3,718.77	\$3,029.69
203	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1.0	LSUM	\$90,000.00	\$90,000.00	\$24,000.00	\$151,390.11	\$94,097.53
204	X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	2,184.0	SQ FT	\$0.50	\$1,092.00	\$0.40	\$0.42	\$0.41
205	X7040125	PINNING TEMPORARY CONCRETE BARRIER	450.0	EACH	\$13.00	\$5,850.00	\$19.00	\$23.00	\$21.25
206	X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	146.0	SQ FT	\$6.00	\$876.00	\$2.00	\$5.00	\$2.77
207	X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	2,975.0	FOOT	\$0.65	\$1,933.75	\$0.45	\$0.60	\$0.49



## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
208	X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	2,357.0	FOOT	\$0.75	\$1,767.75	\$0.55	\$0.80	\$0.62
209	X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	352.0	FOOT	\$0.85	\$299.20	\$0.80	\$1.00	\$0.86
210	X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	84.0	FOOT	\$2.25	\$189.00	\$1.50	\$2.00	\$1.64
211	X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	52.0	FOOT	\$4.00	\$208.00	\$2.00	\$4.00	\$2.52
212	X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	1.0	EACH	\$8,000.00	\$8,000.00	\$4,393.00	\$4,568.72	\$4,436.93
213	X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	1,755.0	FOOT	\$4.00	\$7,020.00	\$3.30	\$3.43	\$3.33
214	XX000856	MAILBOX REMOVAL AND RELOCATION	2.0	EACH	\$300.00	\$600.00	\$100.00	\$852.07	\$325.52
215	XX003668	PRECONSTRUCTION VIDEO TAPING	1.0	LSUM	\$3,500.00	\$3,500.00	\$1,800.00	\$5,000.00	\$2,950.00
216	XX005940	REMOTE CONTROLLED VIDEO SYSTEM	1.0	EACH	\$7,000.00	\$7,000.00	\$4,925.00	\$5,122.00	\$4,974.25
217	XX006522	FURNISH WITNESS POST	4.0	EACH	\$100.00	\$400.00	\$55.00	\$1,330.99	\$459.00
218	XX006658	FLOCCULATION LOGS	100.0	EACH	\$50.00	\$5,000.00	\$0.01	\$1.04	\$0.64
219	XX006659	FLOCCULATION POWDER	20.0	POUND	\$35.00	\$700.00	\$0.01	\$2.00	\$1.01
220	XX008865	PERMEABLE PLASTIC BERM	96.0	FOOT	\$20.00	\$1,920.00	\$12.00	\$15.60	\$14.40

## Return Bid Details

**Project:** Fremont Center Road at IL Route 60

**Section:** 12-00138-02-CH

**Description:** Intersection Improvement including realignment, turn lanes and traffic signal installation

**CPMS Pin:** B-00474C

**Let Date:** 4/13/2021

Item No.	Pay Code	Description	Quantity	Unit	Eng Estimate		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extnd. Price			
221	XX009142	PAVEMENT MARKING REMOVAL (SPECIAL)	567.0	SQ FT	\$1.00	\$567.00	\$0.31	\$0.60	\$0.53
222	XX206400	MAILBOX POST	2.0	EACH	\$150.00	\$300.00	\$150.00	\$200.00	\$187.50
223	Z0007601	BUILDING REMOVAL NO. 1	1.0	L SUM	\$30,000.00	\$30,000.00	\$14,500.00	\$75,956.13	\$33,038.03
224	Z0013797	STABILIZED CONSTRUCTION ENTRANCE	188.0	SQ YD	\$45.00	\$8,460.00	\$20.87	\$32.00	\$27.09
225	Z0013798	CONSTRUCTION LAYOUT	1.0	L SUM	\$36,000.00	\$36,000.00	\$16,500.00	\$97,000.00	\$45,550.00
226	Z0019600	DUST CONTROL WATERING	20.0	UNIT	\$100.00	\$2,000.00	\$1.00	\$100.00	\$62.75
227	Z0022800	FENCE REMOVAL	1,539.0	FOOT	\$5.00	\$7,695.00	\$4.00	\$9.44	\$6.09
228	Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	1.0	EACH	\$10,000.00	\$10,000.00	\$2,355.00	\$2,449.20	\$2,378.55
229	Z0033700	LONGITUDINAL JOINT SEALANT	9,030.0	FOOT	\$2.25	\$20,317.50	\$2.80	\$2.93	\$2.83
230	Z0055905	TEMPORARY CONSTRUCTION FENCE	2,882.0	FOOT	\$4.00	\$11,528.00	\$3.00	\$5.05	\$3.99
231	Z0062450	SAWING PAVEMENT (FULL DEPTH)	4,166.0	FOOT	\$5.00	\$20,830.00	\$2.00	\$2.85	\$2.34
232	Z0062456	TEMPORARY PAVEMENT	446.0	SQ YD	\$60.00	\$26,760.00	\$46.00	\$81.00	\$54.75
233	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	4.0	EACH	\$2,000.00	\$8,000.00	\$485.00	\$504.40	\$489.85
<b>Bid Total</b>					<b>\$2,895,512.95</b>				