



Summary of Bids Received

Project: Darrell Road Intersection Improvements
Section: 13-00107-09-RD

CPMS Pin: B-00141b
Let Date: July 09, 2024

Description: The improvements include modifying the intersections of Darrell Road with Dowell Road and Darrell Road with Fisher Road to provide modern roundabouts. Dowell Road will be re-aligned to the south to provide an intersection closer to ninety degrees with Darrell Road.

Bidder	Address	City, State, Zip	Bid Price	% Over/Under Eng. Estimate	\$ Over/Under Eng. Estimate
Lake County Grading Company, LLC	P.O Box L	Libertyville, IL, 60048	\$7,879,523.93	-20.08%	-\$1,980,046.22
Berger Contractors, Inc.	1205 Garland Road	Wauconda, IL, 60084	\$8,044,042.83	-18.41%	-\$1,815,527.32
Engineer's Estimate:			\$9,859,570.15		



Return Bid Tabulation

Project: Darrell Road Intersection Improvements
Section: 13-00107-09-RD

CPMS Pin: B-00141b
Let Date: July 09, 2024

Description: The improvements include modifying the intersections of Darrell Road with Dowell Road and Darrell Road with Fisher Road to provide modern roundabouts. Dowell Road will be re-aligned to the south to provide an intersection closer to ninety degrees with Darrell Road.

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Lake County Grading Company, LLC		Berger Contractors, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	1,361.00	UNIT	\$23.00	\$31,303.00	\$9.00	\$12,249.00	\$9.00	\$12,249.00
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	801.00	UNIT	\$36.00	\$28,836.00	\$10.00	\$8,010.00	\$10.00	\$8,010.00
3	20100500	TREE REMOVAL, ACRES	2.25	ACRE	\$16,000.00	\$36,000.00	\$2,500.00	\$5,625.00	\$2,500.00	\$5,625.00
4	20101100	TREE TRUNK PROTECTION	38.00	EACH	\$155.00	\$5,890.00	\$90.00	\$3,420.00	\$90.00	\$3,420.00
5	20101200	TREE ROOT PRUNING	38.00	EACH	\$120.00	\$4,560.00	\$80.00	\$3,040.00	\$80.00	\$3,040.00
6	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	11.00	EACH	\$78.00	\$858.00	\$35.00	\$385.00	\$35.00	\$385.00
7	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	27.00	EACH	\$235.00	\$6,345.00	\$70.00	\$1,890.00	\$70.00	\$1,890.00
8	20200100	EARTH EXCAVATION	56,667.00	CU YD	\$17.00	\$963,339.00	\$13.75	\$779,171.25	\$18.45	\$1,045,506.15
9	20400800	FURNISHED EXCAVATION	500.00	CU YD	\$21.00	\$10,500.00	\$0.01	\$5.00	\$1.00	\$500.00
10	20800150	TRENCH BACKFILL	1,131.00	CU YD	\$47.00	\$53,157.00	\$40.00	\$45,240.00	\$33.00	\$37,323.00
11	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	25,055.00	SQ YD	\$2.00	\$50,110.00	\$3.00	\$75,165.00	\$1.85	\$46,351.75
12	21101505	TOPSOIL EXCAVATION AND PLACEMENT	7,805.00	CU YD	\$31.00	\$241,955.00	\$0.01	\$78.05	\$23.00	\$179,515.00
13	21101615	TOPSOIL FURNISH AND PLACE, 4"	500.00	SQ YD	\$5.00	\$2,500.00	\$10.50	\$5,250.00	\$10.50	\$5,250.00
14	21101805	COMPOST FURNISH AND PLACE, 2"	3,234.00	SQ YD	\$4.00	\$12,936.00	\$4.85	\$15,684.90	\$4.85	\$15,684.90
15	25000210	SEEDING, CLASS 2A	6.00	ACRE	\$3,650.00	\$21,900.00	\$1,950.00	\$11,700.00	\$1,950.00	\$11,700.00
16	25000300	SEEDING, CLASS 3	1.00	ACRE	\$4,800.00	\$4,800.00	\$2,020.81	\$2,020.81	\$2,020.81	\$2,020.81
17	25000312	SEEDING, CLASS 4A	2.00	ACRE	\$3,600.00	\$7,200.00	\$1,950.00	\$3,900.00	\$1,950.00	\$3,900.00
18	25000314	SEEDING, CLASS 4B	3.25	ACRE	\$5,200.00	\$16,900.00	\$2,450.00	\$7,962.50	\$2,450.00	\$7,962.50
19	25000400	NITROGEN FERTILIZER NUTRIENT	561.00	POUND	\$3.00	\$1,683.00	\$4.00	\$2,244.00	\$4.00	\$2,244.00
20	25000600	POTASSIUM FERTILIZER NUTRIENT	561.00	POUND	\$3.00	\$1,683.00	\$4.00	\$2,244.00	\$4.00	\$2,244.00
21	25003314	INTERSEEDING, CLASS 4B	3.25	ACRE	\$5,200.00	\$16,900.00	\$2,550.00	\$8,287.50	\$2,550.00	\$8,287.50
22	25100630	EROSION CONTROL BLANKET	55,683.00	SQ YD	\$1.80	\$100,229.40	\$0.90	\$50,114.70	\$0.90	\$50,114.70
23	25100635	HEAVY DUTY EROSION CONTROL BLANKET	3,256.00	SQ YD	\$2.25	\$7,326.00	\$2.35	\$7,651.60	\$2.35	\$7,651.60
24	25200200	SUPPLEMENTAL WATERING	1,889.00	UNIT	\$10.00	\$18,890.00	\$0.01	\$18.89	\$0.01	\$18.89
25	28000250	TEMPORARY EROSION CONTROL SEEDING	1,275.00	POUND	\$8.00	\$10,200.00	\$14.00	\$17,850.00	\$14.00	\$17,850.00
26	28000305	TEMPORARY DITCH CHECKS	574.00	FOOT	\$16.00	\$9,184.00	\$15.50	\$8,897.00	\$15.50	\$8,897.00
27	28000400	PERIMETER EROSION BARRIER	5,516.00	FOOT	\$4.00	\$22,064.00	\$3.45	\$19,030.20	\$3.45	\$19,030.20
28	28000510	INLET FILTERS	34.00	EACH	\$190.00	\$6,460.00	\$250.00	\$8,500.00	\$250.00	\$8,500.00
29	28001100	TEMPORARY EROSION CONTROL BLANKET	61,695.00	SQ YD	\$1.50	\$92,542.50	\$0.01	\$616.95	\$0.01	\$616.95
30	28100105	STONE RIPRAP, CLASS A3	43.00	SQ YD	\$95.00	\$4,085.00	\$91.00	\$3,913.00	\$83.00	\$3,569.00
31	28100107	STONE RIPRAP, CLASS A4	9.00	SQ YD	\$145.00	\$1,305.00	\$156.00	\$1,404.00	\$230.00	\$2,070.00
32	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	23,552.00	SQ YD	\$17.50	\$412,160.00	\$14.00	\$329,728.00	\$18.45	\$434,534.40
33	35101600	AGGREGATE BASE COURSE, TYPE B 4"	2,046.00	SQ YD	\$9.00	\$18,414.00	\$6.60	\$13,503.60	\$4.50	\$9,207.00
34	35101800	AGGREGATE BASE COURSE, TYPE B 6"	2,633.00	SQ YD	\$12.00	\$31,596.00	\$7.50	\$19,747.50	\$8.50	\$22,380.50
35	35102000	AGGREGATE BASE COURSE, TYPE B 8"	357.00	SQ YD	\$13.00	\$4,641.00	\$9.70	\$3,462.90	\$11.00	\$3,927.00
36	40600275	BITUMINOUS MATERIALS (PRIME COAT)	46,966.00	POUND	\$1.00	\$46,966.00	\$0.01	\$469.66	\$0.01	\$469.66
37	40600290	BITUMINOUS MATERIALS (TACK COAT)	8,296.00	POUND	\$1.00	\$8,296.00	\$0.01	\$82.96	\$0.01	\$82.96

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Lake County Grading Company, LLC		Berger Contractors, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
38	40600370	LONGITUDINAL JOINT SEALANT	21,914.00	FOOT	\$3.50	\$76,699.00	\$2.80	\$61,359.20	\$2.80	\$61,359.20
39	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	7,209.00	TON	\$84.00	\$605,556.00	\$74.00	\$533,466.00	\$74.00	\$533,466.00
40	40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	401.00	TON	\$115.00	\$46,115.00	\$142.00	\$56,942.00	\$142.00	\$56,942.00
41	40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	2,064.00	TON	\$100.00	\$206,400.00	\$82.00	\$169,248.00	\$82.00	\$169,248.00
42	42101300	PROTECTIVE COAT	5,871.00	SQ YD	\$2.00	\$11,742.00	\$1.90	\$11,154.90	\$1.90	\$11,154.90
43	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	19,851.00	SQ FT	\$9.50	\$188,584.50	\$8.00	\$158,808.00	\$8.00	\$158,808.00
44	42400800	DETECTABLE WARNINGS	480.00	SQ FT	\$41.00	\$19,680.00	\$38.00	\$18,240.00	\$38.00	\$18,240.00
45	44000100	PAVEMENT REMOVAL	14,700.00	SQ YD	\$15.00	\$220,500.00	\$15.00	\$220,500.00	\$9.70	\$142,590.00
46	44000200	DRIVEWAY PAVEMENT REMOVAL	2,195.00	SQ YD	\$13.00	\$28,535.00	\$0.01	\$21.95	\$4.50	\$9,877.50
47	44000300	CURB REMOVAL	105.00	FOOT	\$10.00	\$1,050.00	\$3.20	\$336.00	\$5.00	\$525.00
48	44000600	SIDEWALK REMOVAL	297.00	SQ FT	\$3.00	\$891.00	\$0.70	\$207.90	\$1.72	\$510.84
49	44201757	CLASS D PATCHES, TYPE III, 9 INCH	23.00	SQ YD	\$100.00	\$2,300.00	\$200.00	\$4,600.00	\$200.00	\$4,600.00
50	48101200	AGGREGATE SHOULDERS, TYPE B	456.00	TON	\$47.00	\$21,432.00	\$52.00	\$23,712.00	\$52.00	\$23,712.00
51	50100100	REMOVAL OF EXISTING STRUCTURES	1.00	EACH	\$5,000.00	\$5,000.00	\$0.01	\$0.01	\$1,000.00	\$1,000.00
52	50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	1.00	EACH	\$480,000.00	\$480,000.00	\$350,000.00	\$350,000.00	\$295,000.00	\$295,000.00
53	52200700	PRECAST MODULAR RETAINING WALL	3,945.00	SQ FT	\$82.00	\$323,490.00	\$68.00	\$268,260.00	\$68.00	\$268,260.00
54	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	10.00	EACH	\$2,100.00	\$21,000.00	\$2,000.00	\$20,000.00	\$1,880.00	\$18,800.00
55	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	8.00	EACH	\$2,300.00	\$18,400.00	\$2,100.00	\$16,800.00	\$1,925.00	\$15,400.00
56	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	1.00	EACH	\$2,600.00	\$2,600.00	\$2,200.00	\$2,200.00	\$2,015.00	\$2,015.00
57	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	1.00	EACH	\$2,800.00	\$2,800.00	\$2,700.00	\$2,700.00	\$2,600.00	\$2,600.00
58	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	3.00	EACH	\$3,100.00	\$9,300.00	\$4,000.00	\$12,000.00	\$4,250.00	\$12,750.00
59	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	164.00	FOOT	\$57.00	\$9,348.00	\$50.00	\$8,200.00	\$63.00	\$10,332.00
60	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	149.00	FOOT	\$62.00	\$9,238.00	\$50.00	\$7,450.00	\$77.00	\$11,473.00
61	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	54.00	FOOT	\$70.00	\$3,780.00	\$59.00	\$3,186.00	\$72.00	\$3,888.00
62	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	2,064.00	FOOT	\$62.00	\$127,968.00	\$41.00	\$84,624.00	\$63.00	\$130,032.00
63	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	141.00	FOOT	\$67.00	\$9,447.00	\$60.00	\$8,460.00	\$84.00	\$11,844.00
64	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	594.00	FOOT	\$72.00	\$42,768.00	\$51.00	\$30,294.00	\$72.00	\$42,768.00
65	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	166.00	FOOT	\$88.00	\$14,608.00	\$62.00	\$10,292.00	\$98.00	\$16,268.00
66	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	179.00	FOOT	\$125.00	\$22,375.00	\$126.00	\$22,554.00	\$174.00	\$31,146.00
67	55100100	STORM SEWER REMOVAL 4"	32.00	FOOT	\$20.00	\$640.00	\$10.00	\$320.00	\$20.00	\$640.00
68	55100400	STORM SEWER REMOVAL 10"	40.00	FOOT	\$21.00	\$840.00	\$10.00	\$400.00	\$20.00	\$800.00
69	55100500	STORM SEWER REMOVAL 12"	111.00	FOOT	\$22.00	\$2,442.00	\$22.00	\$2,442.00	\$20.00	\$2,220.00
70	55100700	STORM SEWER REMOVAL 15"	142.00	FOOT	\$24.00	\$3,408.00	\$22.00	\$3,124.00	\$20.00	\$2,840.00
71	55100900	STORM SEWER REMOVAL 18"	153.00	FOOT	\$25.00	\$3,825.00	\$22.00	\$3,366.00	\$20.00	\$3,060.00
72	55101200	STORM SEWER REMOVAL 24"	112.00	FOOT	\$30.00	\$3,360.00	\$22.00	\$2,464.00	\$20.00	\$2,240.00
73	60100905	PIPE DRAINS 4"	200.00	FOOT	\$40.00	\$8,000.00	\$20.00	\$4,000.00	\$16.00	\$3,200.00
74	60100915	PIPE DRAINS 6"	200.00	FOOT	\$45.00	\$9,000.00	\$20.00	\$4,000.00	\$20.00	\$4,000.00
75	60108104	PIPE UNDERDRAINS, TYPE 1, 4"	11,563.00	FOOT	\$10.00	\$115,630.00	\$6.00	\$69,378.00	\$6.50	\$75,159.50
76	60146304	PIPE UNDERDRAINS FOR STRUCTURES 4"	407.00	FOOT	\$36.00	\$14,652.00	\$39.00	\$15,873.00	\$19.85	\$8,078.95
77	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	16.00	EACH	\$4,400.00	\$70,400.00	\$3,100.00	\$49,600.00	\$3,500.00	\$56,000.00
78	60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	1.00	EACH	\$6,200.00	\$6,200.00	\$5,000.00	\$5,000.00	\$6,400.00	\$6,400.00
79	60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	2.00	EACH	\$2,300.00	\$4,600.00	\$2,000.00	\$4,000.00	\$2,250.00	\$4,500.00
80	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	5.00	EACH	\$2,300.00	\$11,500.00	\$1,900.00	\$9,500.00	\$1,820.00	\$9,100.00
81	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	18.00	EACH	\$2,300.00	\$41,400.00	\$2,300.00	\$41,400.00	\$2,300.00	\$41,400.00
82	60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	1.00	EACH	\$4,400.00	\$4,400.00	\$3,100.00	\$3,100.00	\$3,400.00	\$3,400.00
83	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	8.00	EACH	\$4,400.00	\$35,200.00	\$3,100.00	\$24,800.00	\$3,325.00	\$26,600.00
84	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	5.00	EACH	\$5,200.00	\$26,000.00	\$4,200.00	\$21,000.00	\$5,600.00	\$28,000.00
85	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	2.00	EACH	\$9,000.00	\$18,000.00	\$6,700.00	\$13,400.00	\$8,650.00	\$17,300.00

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Lake County Grading Company, LLC		Berger Contractors, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
86	60500050	REMOVING CATCH BASINS	1.00	EACH	\$775.00	\$775.00	\$600.00	\$600.00	\$650.00	\$650.00
87	60600605	CONCRETE CURB, TYPE B	883.00	FOOT	\$46.00	\$40,618.00	\$48.00	\$42,384.00	\$44.00	\$38,852.00
88	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	4,039.00	FOOT	\$41.00	\$165,599.00	\$33.00	\$133,287.00	\$31.00	\$125,209.00
89	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	3,278.00	FOOT	\$46.00	\$150,788.00	\$41.00	\$134,398.00	\$39.00	\$127,842.00
90	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	684.00	FOOT	\$42.00	\$28,728.00	\$47.00	\$32,148.00	\$46.00	\$31,464.00
91	60619600	CONCRETE MEDIAN, TYPE SB-6.12	348.00	SQ FT	\$21.00	\$7,308.00	\$24.00	\$8,352.00	\$24.00	\$8,352.00
92	63200310	GUARDRAIL REMOVAL	31.00	FOOT	\$8.00	\$248.00	\$12.40	\$384.40	\$15.00	\$465.00
93	64200108	SHOULDER RUMBLE STRIPS, 8 INCH	3,646.00	FOOT	\$1.00	\$3,646.00	\$1.30	\$4,739.80	\$1.20	\$4,375.20
94	66900200	NON-SPECIAL WASTE DISPOSAL	1,650.00	CU YD	\$80.00	\$132,000.00	\$55.00	\$90,750.00	\$0.01	\$16.50
95	66900530	SOIL DISPOSAL ANALYSIS	2.00	EACH	\$1,800.00	\$3,600.00	\$1,450.00	\$2,900.00	\$1,600.00	\$3,200.00
96	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	1.00	L SUM	\$3,600.00	\$3,600.00	\$5,300.00	\$5,300.00	\$4,000.00	\$4,000.00
97	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	1.00	L SUM	\$2,000.00	\$2,000.00	\$500.00	\$500.00	\$2,500.00	\$2,500.00
98	66901006	REGULATED SUBSTANCES MONITORING	60.00	CAL DA	\$750.00	\$45,000.00	\$0.01	\$0.60	\$125.00	\$7,500.00
99	67100100	MOBILIZATION	1.00	L SUM	\$555,000.00	\$555,000.00	\$468,000.00	\$468,000.00	\$482,000.00	\$482,000.00
100	67201000	SEALING ABANDONED WATER WELLS	2.00	EACH	\$5,200.00	\$10,400.00	\$1,500.00	\$3,000.00	\$2,600.00	\$5,200.00
101	70107025	CHANGEABLE MESSAGE SIGN	336.00	CAL DA	\$30.00	\$10,080.00	\$27.00	\$9,072.00	\$27.00	\$9,072.00
102	70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	178.00	SQ FT	\$1.00	\$178.00	\$2.00	\$356.00	\$2.00	\$356.00
103	70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	16,141.00	FOOT	\$0.30	\$4,842.30	\$0.35	\$5,649.35	\$0.35	\$5,649.35
104	70300231	TEMPORARY PAVEMENT MARKING - LINE 5"- PAINT	9,051.00	FOOT	\$0.35	\$3,167.85	\$0.40	\$3,620.40	\$0.40	\$3,620.40
105	70300251	TEMPORARY PAVEMENT MARKING - LINE 8"- PAINT	679.00	FOOT	\$0.60	\$407.40	\$0.70	\$475.30	\$0.70	\$475.30
106	70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	1,043.00	FOOT	\$1.00	\$1,043.00	\$1.00	\$1,043.00	\$1.00	\$1,043.00
107	70307100	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - TYPE IV TAPE	134.00	SQ FT	\$5.00	\$670.00	\$0.38	\$50.92	\$3.75	\$502.50
108	70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	12,039.00	FOOT	\$1.00	\$12,039.00	\$0.40	\$4,815.60	\$0.40	\$4,815.60
109	70307125	TEMPORARY PAVEMENT MARKING - LINE 5" - TYPE IV TAPE	9,051.00	FOOT	\$1.25	\$11,313.75	\$0.50	\$4,525.50	\$0.50	\$4,525.50
110	70307140	TEMPORARY PAVEMENT MARKING - LINE 8" - TYPE IV TAPE	679.00	FOOT	\$1.75	\$1,188.25	\$2.40	\$1,629.60	\$2.40	\$1,629.60
111	70307160	TEMPORARY PAVEMENT MARKING - LINE 12"- TYPE IV TAPE	1,043.00	FOOT	\$2.50	\$2,607.50	\$3.60	\$3,754.80	\$3.60	\$3,754.80
112	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	30.00	EACH	\$50.00	\$1,500.00	\$40.00	\$1,200.00	\$40.00	\$1,200.00
113	72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	10.00	EACH	\$100.00	\$1,000.00	\$50.00	\$500.00	\$50.00	\$500.00
114	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	1.00	EACH	\$150.00	\$150.00	\$150.00	\$150.00	\$150.00	\$150.00
115	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	1.00	EACH	\$250.00	\$250.00	\$200.00	\$200.00	\$200.00	\$200.00
116	72800100	TELESCOPING STEEL SIGN SUPPORT	34.00	FOOT	\$20.00	\$680.00	\$20.00	\$680.00	\$20.00	\$680.00
117	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	134.00	SQ FT	\$6.00	\$804.00	\$6.00	\$804.00	\$6.00	\$804.00
118	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	2,446.00	FOOT	\$1.00	\$2,446.00	\$1.00	\$2,446.00	\$1.00	\$2,446.00
119	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	3,808.00	FOOT	\$1.25	\$4,760.00	\$1.25	\$4,760.00	\$1.25	\$4,760.00
120	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	951.00	FOOT	\$2.50	\$2,377.50	\$3.00	\$2,853.00	\$3.00	\$2,853.00
121	78004620	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 4"	8,987.00	FOOT	\$5.00	\$44,935.00	\$4.00	\$35,948.00	\$4.00	\$35,948.00
122	78004625	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 5"	5,243.00	FOOT	\$6.00	\$31,458.00	\$4.25	\$22,282.75	\$4.25	\$22,282.75
123	78004640	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 8"	679.00	FOOT	\$9.00	\$6,111.00	\$8.00	\$5,432.00	\$8.00	\$5,432.00
124	78004660	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 12"	92.00	FOOT	\$15.00	\$1,380.00	\$12.00	\$1,104.00	\$12.00	\$1,104.00
125	78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	594.00	FOOT	\$10.00	\$5,940.00	\$4.00	\$2,376.00	\$4.00	\$2,376.00
126	78011000	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	158.00	SQ FT	\$6.00	\$948.00	\$3.00	\$474.00	\$3.00	\$474.00
127	78011025	GROOVING FOR RECESSED PAVEMENT MARKING 5"	8,987.00	FOOT	\$0.60	\$5,392.20	\$0.45	\$4,044.15	\$0.45	\$4,044.15

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Lake County Grading Company, LLC		Berger Contractors, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
128	78011030	GROOVING FOR RECESSED PAVEMENT MARKING 6"	7,380.00	FOOT	\$0.65	\$4,797.00	\$0.50	\$3,690.00	\$0.50	\$3,690.00
129	78011045	GROOVING FOR RECESSED PAVEMENT MARKING 9"	679.00	FOOT	\$2.50	\$1,697.50	\$1.00	\$679.00	\$1.00	\$679.00
130	78011065	GROOVING FOR RECESSED PAVEMENT MARKING 13"	980.00	FOOT	\$3.25	\$3,185.00	\$1.25	\$1,225.00	\$1.25	\$1,225.00
131	78300201	PAVEMENT MARKING REMOVAL - GRINDING	25.00	SQ FT	\$2.50	\$62.50	\$5.00	\$125.00	\$5.00	\$125.00
132	80400100	ELECTRIC SERVICE INSTALLATION	2.00	EACH	\$4,000.00	\$8,000.00	\$5,014.00	\$10,028.00	\$4,068.71	\$8,137.42
133	80400200	ELECTRIC UTILITY SERVICE CONNECTION	1.00	L SUM	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00
134	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	2,589.00	FOOT	\$22.50	\$58,252.50	\$31.10	\$80,517.90	\$23.13	\$59,883.57
135	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	150.00	FOOT	\$33.00	\$4,950.00	\$54.30	\$8,145.00	\$38.74	\$5,811.00
136	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	400.00	FOOT	\$36.00	\$14,400.00	\$63.30	\$25,320.00	\$40.41	\$16,164.00
137	81400100	HANDHOLE	4.00	EACH	\$1,900.00	\$7,600.00	\$2,363.00	\$9,452.00	\$3,362.61	\$13,450.44
138	81400200	HEAVY-DUTY HANDHOLE	4.00	EACH	\$4,200.00	\$16,800.00	\$5,249.00	\$20,996.00	\$3,807.44	\$15,229.76
139	81603096	UNIT DUCT, 600V, 4-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	3,809.00	FOOT	\$16.00	\$60,944.00	\$25.70	\$97,891.30	\$16.99	\$64,714.91
140	81603100	UNIT DUCT, 600V, 4-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	3,699.00	FOOT	\$19.00	\$70,281.00	\$28.10	\$103,941.90	\$19.17	\$70,909.83
141	81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	160.00	FOOT	\$13.00	\$2,080.00	\$14.90	\$2,384.00	\$11.07	\$1,771.20
142	81800240	AERIAL CABLE, 2-1/C NO. 8 WITH MESSENGER WIRE	6,840.00	FOOT	\$5.00	\$34,200.00	\$1.70	\$11,628.00	\$1.50	\$10,260.00
143	82110004	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION D	25.00	EACH	\$750.00	\$18,750.00	\$694.70	\$17,367.50	\$711.99	\$17,799.75
144	82110006	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION F	17.00	EACH	\$750.00	\$12,750.00	\$760.30	\$12,925.10	\$690.82	\$11,743.94
145	82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	1.00	EACH	\$57,500.00	\$57,500.00	\$51,871.00	\$51,871.00	\$16,024.11	\$16,024.11
146	83057175	LIGHT POLE, WOOD, 35 FOOT, CLASS 3, WITH 15FT MAST ARM	2.00	EACH	\$2,100.00	\$4,200.00	\$519.00	\$1,038.00	\$1.00	\$2.00
147	83057215	LIGHT POLE, WOOD, 40 FOOT, CLASS 3, WITH 15FT MAST ARM	40.00	EACH	\$2,300.00	\$92,000.00	\$519.00	\$20,760.00	\$1.00	\$40.00
148	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	420.00	FOOT	\$310.00	\$130,200.00	\$358.30	\$150,486.00	\$429.07	\$180,209.40
149	83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	28.00	EACH	\$725.00	\$20,300.00	\$980.00	\$27,440.00	\$635.59	\$17,796.52
150	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	43.00	EACH	\$525.00	\$22,575.00	\$181.00	\$7,783.00	\$1.00	\$43.00
151	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	5,037.00	FOOT	\$1.00	\$5,037.00	\$1.10	\$5,540.70	\$2.21	\$11,131.77
152	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	486.00	FOOT	\$4.50	\$2,187.00	\$5.30	\$2,575.80	\$6.15	\$2,988.90
153	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	546.00	FOOT	\$2.60	\$1,419.60	\$2.70	\$1,474.20	\$5.08	\$2,773.68
154	87800100	CONCRETE FOUNDATION, TYPE A	12.00	FOOT	\$260.00	\$3,120.00	\$346.80	\$4,161.60	\$299.29	\$3,591.48
155	A2002016	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2" CALIPER, BALLED AND BURLAPPED	3.00	EACH	\$850.00	\$2,550.00	\$680.00	\$2,040.00	\$680.00	\$2,040.00
156	A2002924	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 3" CALIPER, BALLED AND BURLAPPED	13.00	EACH	\$850.00	\$11,050.00	\$590.00	\$7,670.00	\$590.00	\$7,670.00
157	A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	4.00	EACH	\$850.00	\$3,400.00	\$587.50	\$2,350.00	\$587.50	\$2,350.00
158	A2005024	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 3" CALIPER, BALLED AND BURLAPPED	10.00	EACH	\$850.00	\$8,500.00	\$642.50	\$6,425.00	\$642.50	\$6,425.00
159	A2005116	TREE, JUGLANS NIGRA (BLACK WALNUT), 2" CALIPER, BALLED AND BURLAPPED	3.00	EACH	\$850.00	\$2,550.00	\$612.50	\$1,837.50	\$612.50	\$1,837.50
160	A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	8.00	EACH	\$850.00	\$6,800.00	\$575.00	\$4,600.00	\$575.00	\$4,600.00
161	A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	22.00	EACH	\$850.00	\$18,700.00	\$575.00	\$12,650.00	\$575.00	\$12,650.00
162	A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	7.00	EACH	\$850.00	\$5,950.00	\$575.00	\$4,025.00	\$575.00	\$4,025.00
163	A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	26.00	EACH	\$850.00	\$22,100.00	\$575.00	\$14,950.00	\$575.00	\$14,950.00
164	A2007624	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 3" CALIPER, BALLED AND BURLAPPED	17.00	EACH	\$850.00	\$14,450.00	\$700.00	\$11,900.00	\$700.00	\$11,900.00
165	LC100101	UTILITY MONITORING	25,000.00	UNIT	\$1.00	\$25,000.00	\$1.00	\$25,000.00	\$1.00	\$25,000.00

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Lake County Grading Company, LLC		Berger Contractors, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
166	LC200051	REJECTED LOAD TRANSPORTATION	10.00	LOAD	\$300.00	\$3,000.00	\$0.01	\$0.10	\$60.00	\$600.00
167	LC200200	TREE, SPECIAL	16.00	EACH	\$850.00	\$13,600.00	\$592.50	\$9,480.00	\$592.50	\$9,480.00
168	LC200320	SHRUB, SPECIAL	40.00	EACH	\$90.00	\$3,600.00	\$53.83	\$2,153.20	\$53.83	\$2,153.20
169	LC200321	SHRUB, SPECIAL I	117.00	EACH	\$90.00	\$10,530.00	\$66.25	\$7,751.25	\$66.25	\$7,751.25
170	LC200322	SHRUB, SPECIAL II	26.00	EACH	\$90.00	\$2,340.00	\$70.00	\$1,820.00	\$70.00	\$1,820.00
171	LC200323	SHRUB, SPECIAL III	12.00	EACH	\$90.00	\$1,080.00	\$69.00	\$828.00	\$69.00	\$828.00
172	LC200360	PERENNIAL PLANTINGS, SPECIAL I	946.00	EACH	\$18.00	\$17,028.00	\$14.30	\$13,527.80	\$14.30	\$13,527.80
173	LC200361	PERENNIAL PLANTINGS, SPECIAL II	88.00	EACH	\$18.00	\$1,584.00	\$12.94	\$1,138.72	\$12.94	\$1,138.72
174	LC200362	PERENNIAL PLANTINGS, SPECIAL III	116.00	EACH	\$18.00	\$2,088.00	\$13.00	\$1,508.00	\$13.00	\$1,508.00
175	LC200363	PERENNIAL PLANTINGS, SPECIAL IV	659.00	EACH	\$18.00	\$11,862.00	\$21.00	\$13,839.00	\$21.00	\$13,839.00
176	LC200364	PERENNIAL PLANTINGS, SPECIAL V	522.00	EACH	\$18.00	\$9,396.00	\$16.10	\$8,404.20	\$16.10	\$8,404.20
177	LC200365	PERENNIAL PLANTINGS, SPECIAL VI	1,608.00	UNIT	\$18.00	\$28,944.00	\$11.06	\$17,784.48	\$11.06	\$17,784.48
178	LC200366	PERENNIAL PLANTINGS, SPECIAL VII	50.00	UNIT	\$18.00	\$900.00	\$16.10	\$805.00	\$16.10	\$805.00
179	LC200367	PERENNIAL PLANTINGS, SPECIAL VIII	40.00	UNIT	\$18.00	\$720.00	\$13.00	\$520.00	\$13.00	\$520.00
180	LC200501	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	39,155.00	UNIT	\$1.00	\$39,155.00	\$1.00	\$39,155.00	\$1.00	\$39,155.00
181	LC351001	AGGREGATE BASE COURSE, TYPE B 2.5"	1,590.00	SQ YD	\$6.00	\$9,540.00	\$1.50	\$2,385.00	\$3.25	\$5,167.50
182	LC442009	TACTILE DIRECTIONAL INDICATOR	342.00	SQ FT	\$40.00	\$13,680.00	\$36.00	\$12,312.00	\$36.00	\$12,312.00
183	LC500230	GRATING FOR CONCRETE FLARED END SECTION 24"	1.00	EACH	\$1,600.00	\$1,600.00	\$650.00	\$650.00	\$1,115.00	\$1,115.00
184	LC500234	GRATING FOR CONCRETE FLARED END SECTION 36"	3.00	EACH	\$1,800.00	\$5,400.00	\$1,100.00	\$3,300.00	\$2,625.00	\$7,875.00
185	LC500418	CAST-IN-PLACE CONCRETE WALL CAP	365.00	FOOT	\$210.00	\$76,650.00	\$312.00	\$113,880.00	\$312.00	\$113,880.00
186	LC600029	PERFORATED RISER PIPE	3.00	EACH	\$4,100.00	\$12,300.00	\$5,000.00	\$15,000.00	\$5,100.00	\$15,300.00
187	LC600200	INSTALL SURVEY MONUMENTS	2.00	EACH	\$575.00	\$1,150.00	\$500.00	\$1,000.00	\$550.00	\$1,100.00
188	LC800266	TEMPORARY LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION D	25.00	EACH	\$775.00	\$19,375.00	\$230.00	\$5,750.00	\$50.00	\$1,250.00
189	LC800267	TEMPORARY LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION F	17.00	EACH	\$925.00	\$15,725.00	\$230.00	\$3,910.00	\$55.00	\$935.00
190	X0324597	CLOSED CIRCUIT TELEVISION CABINET	2.00	EACH	\$8,250.00	\$16,500.00	\$13,443.00	\$26,886.00	\$12,748.91	\$25,497.82
191	X0326898	CENTER LINE - RUMBLE STRIP - 16"	1,068.00	FOOT	\$1.30	\$1,388.40	\$4.09	\$4,368.12	\$3.00	\$3,204.00
192	X0327349	TEMPORARY WOOD POLE, 40 FT., CLASS 4	1.00	EACH	\$2,100.00	\$2,100.00	\$519.00	\$519.00	\$1,915.33	\$1,915.33
193	X0426200	DEWATERING	1.00	L SUM	\$35,000.00	\$35,000.00	\$150,000.00	\$150,000.00	\$27,000.00	\$27,000.00
194	X0488100	REMOVING EXISTING SEPTIC TANK	2.00	EACH	\$5,000.00	\$10,000.00	\$2,000.00	\$4,000.00	\$1,300.00	\$2,600.00
195	X1400007	FIBER OPTIC CABLE IN CONDUIT, 24 FIBERS, SINGLE MODE	5,083.00	FOOT	\$4.00	\$20,332.00	\$4.20	\$21,348.60	\$4.21	\$21,399.43
196	X1400102	OUTDOOR RATED NETWORK CABLE	147.00	FOOT	\$3.50	\$514.50	\$4.20	\$617.40	\$3.15	\$463.05
197	X1400150	SERVICE INSTALLATION, GROUND MOUNTED, METERED	1.00	EACH	\$2,500.00	\$2,500.00	\$3,841.00	\$3,841.00	\$3,772.58	\$3,772.58
198	X1400216	LAYER II (DATALINK) SWITCH	2.00	EACH	\$5,500.00	\$11,000.00	\$5,293.00	\$10,586.00	\$4,671.44	\$9,342.88
199	X1700112	BRICK PAVER REMOVAL	542.00	SQ FT	\$10.00	\$5,420.00	\$1.58	\$856.36	\$2.00	\$1,084.00
200	X2070304	POROUS GRANULAR EMBANKMENT (SPECIAL)	2,668.00	CU YD	\$56.00	\$149,408.00	\$44.00	\$117,392.00	\$57.00	\$152,076.00
201	X2130010	EXPLORATION TRENCH (SPECIAL)	300.00	FOOT	\$25.00	\$7,500.00	\$20.00	\$6,000.00	\$16.00	\$4,800.00
202	X2200018	ORNAMENTAL FENCE	365.00	FOOT	\$210.00	\$76,650.00	\$123.91	\$45,227.15	\$123.91	\$45,227.15
203	X2800500	INLET PROTECTION (SPECIAL)	7.00	EACH	\$290.00	\$2,030.00	\$150.00	\$1,050.00	\$350.00	\$2,450.00
204	X3110102	COARSE AGGREGATE BACKFILL (SPECIAL)	1,811.00	CU YD	\$40.00	\$72,440.00	\$55.00	\$99,605.00	\$0.10	\$181.10
205	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	4.00	EACH	\$1,000.00	\$4,000.00	\$500.00	\$2,000.00	\$1,000.00	\$4,000.00
206	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	2.00	EACH	\$1,500.00	\$3,000.00	\$500.00	\$1,000.00	\$1,700.00	\$3,400.00
207	X4023000	TEMPORARY ACCESS (ROAD)	3.00	EACH	\$5,000.00	\$15,000.00	\$1,000.00	\$3,000.00	\$3,100.00	\$9,300.00
208	X5020100	AGGREGATE COLUMN GROUND IMPROVEMENT	1.00	L SUM	\$260,000.00	\$260,000.00	\$260,000.00	\$260,000.00	\$305,000.00	\$305,000.00
209	X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	3.00	EACH	\$15,000.00	\$45,000.00	\$16,000.00	\$48,000.00	\$17,000.00	\$51,000.00
210	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	18.00	CAL MO	\$4,000.00	\$72,000.00	\$2,500.00	\$45,000.00	\$4,000.00	\$72,000.00
211	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	1.00	L SUM	\$285,000.00	\$285,000.00	\$63,000.00	\$63,000.00	\$190,300.00	\$190,300.00

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Lake County Grading Company, LLC		Berger Contractors, Inc.	
					Unit Price	Extnd. Price	Unit Price	Extnd. Price	Unit Price	Extnd. Price
212	X7800815	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	606.00	FOOT	\$0.50	\$303.00	\$5.00	\$3,030.00	\$5.00	\$3,030.00
213	X8040104	TEMPORARY ELECTRIC SERVICE INSTALLATION	1.00	EACH	\$2,000.00	\$2,000.00	\$1,150.00	\$1,150.00	\$4,586.21	\$4,586.21
214	X8210405	LUMINAIRE SHIELD	2.00	EACH	\$500.00	\$1,000.00	\$270.50	\$541.00	\$209.44	\$418.88
215	X8250060	TEMPORARY LIGHTING CONTROLLER	1.00	EACH	\$10,000.00	\$10,000.00	\$519.00	\$519.00	\$1.00	\$1.00
216	X8300001	LIGHT POLE (SPECIAL)	40.00	EACH	\$11,500.00	\$460,000.00	\$10,193.00	\$407,720.00	\$9,593.59	\$383,743.60
217	X8440102	RELOCATE EXISTING LUMINAIRE	42.00	EACH	\$525.00	\$22,050.00	\$83.00	\$3,486.00	\$458.28	\$19,247.76
218	XX000856	MAILBOX REMOVAL AND RELOCATION	4.00	EACH	\$475.00	\$1,900.00	\$400.00	\$1,600.00	\$400.00	\$1,600.00
219	XX003668	PRECONSTRUCTION VIDEO TAPING	1.00	L SUM	\$8,000.00	\$8,000.00	\$1,495.00	\$1,495.00	\$2,400.00	\$2,400.00
220	XX005940	REMOTE CONTROLLED VIDEO SYSTEM	2.00	EACH	\$6,000.00	\$12,000.00	\$7,135.00	\$14,270.00	\$8,238.61	\$16,477.22
221	XX006522	FURNISH WITNESS POST	46.00	EACH	\$180.00	\$8,280.00	\$50.00	\$2,300.00	\$150.00	\$6,900.00
222	XX006652	STAMPED COLORED PORTLAND CEMENT CONCRETE MEDIAN SURFACE 4 INCH (SPECIAL)	4,217.00	SQ FT	\$21.00	\$88,557.00	\$15.55	\$65,574.35	\$15.00	\$63,255.00
223	XX006658	FLOCCULATION LOGS	10.00	EACH	\$120.00	\$1,200.00	\$1.00	\$10.00	\$1.00	\$10.00
224	XX006659	FLOCCULATION POWDER	10.00	POUND	\$20.00	\$200.00	\$1.00	\$10.00	\$1.00	\$10.00
225	XX006898	STAMPED COLORED PORTLAND CEMENT CONCRETE	7,828.00	SQ FT	\$26.00	\$203,528.00	\$24.35	\$190,611.80	\$23.00	\$180,044.00
226	XX008824	CATCH BASINS, SPECIAL	8.00	EACH	\$3,100.00	\$24,800.00	\$1,100.00	\$8,800.00	\$1,850.00	\$14,800.00
227	XX008865	PERMEABLE PLASTIC BERM	574.00	FOOT	\$16.00	\$9,184.00	\$15.00	\$8,610.00	\$18.00	\$10,332.00
228	XX009135	LIGHT POLE, SPECIAL, TYPE 2	2.00	EACH	\$11,000.00	\$22,000.00	\$9,720.00	\$19,440.00	\$10,091.54	\$20,183.08
229	XX009142	PAVEMENT MARKING REMOVAL (SPECIAL)	9,414.00	SQ FT	\$1.00	\$9,414.00	\$0.60	\$5,648.40	\$0.60	\$5,648.40
230	Z0007601	BUILDING REMOVAL NO. 1	1.00	L SUM	\$50,000.00	\$50,000.00	\$50,000.00	\$50,000.00	\$22,000.00	\$22,000.00
231	Z0007602	BUILDING REMOVAL NO. 2	1.00	L SUM	\$25,000.00	\$25,000.00	\$30,000.00	\$30,000.00	\$15,000.00	\$15,000.00
232	Z0007603	BUILDING REMOVAL NO. 3	1.00	L SUM	\$5,000.00	\$5,000.00	\$20,000.00	\$20,000.00	\$7,000.00	\$7,000.00
233	Z0007604	BUILDING REMOVAL NO. 4	1.00	L SUM	\$25,000.00	\$25,000.00	\$30,000.00	\$30,000.00	\$14,000.00	\$14,000.00
234	Z0013797	STABILIZED CONSTRUCTION ENTRANCE	311.00	SQ YD	\$40.00	\$12,440.00	\$25.00	\$7,775.00	\$40.00	\$12,440.00
235	Z0013798	CONSTRUCTION LAYOUT	1.00	L SUM	\$100,000.00	\$100,000.00	\$83,000.00	\$83,000.00	\$47,000.00	\$47,000.00
236	Z0019600	DUST CONTROL WATERING	100.00	UNIT	\$100.00	\$10,000.00	\$100.00	\$10,000.00	\$1.00	\$100.00
237	Z0022800	FENCE REMOVAL	2,780.00	FOOT	\$5.00	\$13,900.00	\$4.93	\$13,705.40	\$4.50	\$12,510.00
238	Z0030850	TEMPORARY INFORMATION SIGNING	150.00	SQ FT	\$16.00	\$2,400.00	\$20.00	\$3,000.00	\$20.00	\$3,000.00
239	Z0055905	TEMPORARY CONSTRUCTION FENCE	2,000.00	FOOT	\$3.50	\$7,000.00	\$3.81	\$7,620.00	\$4.00	\$8,000.00
240	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	5.00	EACH	\$1,250.00	\$6,250.00	\$1,436.00	\$7,180.00	\$500.00	\$2,500.00
					Total	\$9,859,570.15		\$7,879,523.93		\$8,044,042.83



Return Bid Details

Project: Darrell Road Intersection Improvements
Section: 13-00107-09-RD

CPMS Pin: B-00141b
Let Date: July 09, 2024

Description: The improvements include modifying the intersections of Darrell Road with Dowell Road and Darrell Road with Fisher Road to provide modern roundabouts. Dowell Road will be re-aligned to the south to provide an intersection closer to ninety degrees with Darrell Road.

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extn'd. Price			
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	1361.00	UNIT	\$23.00	\$31,303.00	\$9.00	\$9.00	\$9.00
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	801.00	UNIT	\$36.00	\$28,836.00	\$10.00	\$10.00	\$10.00
3	20100500	TREE REMOVAL, ACRES	2.25	ACRE	\$16,000.00	\$36,000.00	\$2,500.00	\$2,500.00	\$2,500.00
4	20101100	TREE TRUNK PROTECTION	38.00	EACH	\$155.00	\$5,890.00	\$90.00	\$90.00	\$90.00
5	20101200	TREE ROOT PRUNING	38.00	EACH	\$120.00	\$4,560.00	\$80.00	\$80.00	\$80.00
6	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	11.00	EACH	\$78.00	\$858.00	\$35.00	\$35.00	\$35.00
7	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	27.00	EACH	\$235.00	\$6,345.00	\$70.00	\$70.00	\$70.00
8	20200100	EARTH EXCAVATION	56667.00	CU YD	\$17.00	\$963,339.00	\$13.75	\$18.45	\$16.10
9	20400800	FURNISHED EXCAVATION	500.00	CU YD	\$21.00	\$10,500.00	\$0.01	\$1.00	\$0.50
10	20800150	TRENCH BACKFILL	1131.00	CU YD	\$47.00	\$53,157.00	\$33.00	\$40.00	\$36.50
11	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	25055.00	SQ YD	\$2.00	\$50,110.00	\$1.85	\$3.00	\$2.42
12	21101505	TOPSOIL EXCAVATION AND PLACEMENT	7805.00	CU YD	\$31.00	\$241,955.00	\$0.01	\$23.00	\$11.50
13	21101615	TOPSOIL FURNISH AND PLACE, 4"	500.00	SQ YD	\$5.00	\$2,500.00	\$10.50	\$10.50	\$10.50
14	21101805	COMPOST FURNISH AND PLACE, 2"	3234.00	SQ YD	\$4.00	\$12,936.00	\$4.85	\$4.85	\$4.85
15	25000210	SEEDING, CLASS 2A	6.00	ACRE	\$3,650.00	\$21,900.00	\$1,950.00	\$1,950.00	\$1,950.00
16	25000300	SEEDING, CLASS 3	1.00	ACRE	\$4,800.00	\$4,800.00	\$2,020.81	\$2,020.81	\$2,020.81
17	25000312	SEEDING, CLASS 4A	2.00	ACRE	\$3,600.00	\$7,200.00	\$1,950.00	\$1,950.00	\$1,950.00
18	25000314	SEEDING, CLASS 4B	3.25	ACRE	\$5,200.00	\$16,900.00	\$2,450.00	\$2,450.00	\$2,450.00
19	25000400	NITROGEN FERTILIZER NUTRIENT	561.00	POUND	\$3.00	\$1,683.00	\$4.00	\$4.00	\$4.00
20	25000600	POTASSIUM FERTILIZER NUTRIENT	561.00	POUND	\$3.00	\$1,683.00	\$4.00	\$4.00	\$4.00
21	25003314	INTERSEEDING, CLASS 4B	3.25	ACRE	\$5,200.00	\$16,900.00	\$2,550.00	\$2,550.00	\$2,550.00
22	25100630	EROSION CONTROL BLANKET	55683.00	SQ YD	\$1.80	\$100,229.40	\$0.90	\$0.90	\$0.90
23	25100635	HEAVY DUTY EROSION CONTROL BLANKET	3256.00	SQ YD	\$2.25	\$7,326.00	\$2.35	\$2.35	\$2.35
24	25200200	SUPPLEMENTAL WATERING	1889.00	UNIT	\$10.00	\$18,890.00	\$0.01	\$0.01	\$0.01
25	28000250	TEMPORARY EROSION CONTROL SEEDING	1275.00	POUND	\$8.00	\$10,200.00	\$14.00	\$14.00	\$14.00
26	28000305	TEMPORARY DITCH CHECKS	574.00	FOOT	\$16.00	\$9,184.00	\$15.50	\$15.50	\$15.50
27	28000400	PERIMETER EROSION BARRIER	5516.00	FOOT	\$4.00	\$22,064.00	\$3.45	\$3.45	\$3.45
28	28000510	INLET FILTERS	34.00	EACH	\$190.00	\$6,460.00	\$250.00	\$250.00	\$250.00
29	28001100	TEMPORARY EROSION CONTROL BLANKET	61695.00	SQ YD	\$1.50	\$92,542.50	\$0.01	\$0.01	\$0.01
30	28100105	STONE RIPRAP, CLASS A3	43.00	SQ YD	\$95.00	\$4,085.00	\$83.00	\$91.00	\$87.00
31	28100107	STONE RIPRAP, CLASS A4	9.00	SQ YD	\$145.00	\$1,305.00	\$156.00	\$230.00	\$193.00
32	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	23552.00	SQ YD	\$17.50	\$412,160.00	\$14.00	\$18.45	\$16.22
33	35101600	AGGREGATE BASE COURSE, TYPE B 4"	2046.00	SQ YD	\$9.00	\$18,414.00	\$4.50	\$6.60	\$5.55
34	35101800	AGGREGATE BASE COURSE, TYPE B 6"	2633.00	SQ YD	\$12.00	\$31,596.00	\$7.50	\$8.50	\$8.00
35	35102000	AGGREGATE BASE COURSE, TYPE B 8"	357.00	SQ YD	\$13.00	\$4,641.00	\$9.70	\$11.00	\$10.35
36	40600275	BITUMINOUS MATERIALS (PRIME COAT)	46966.00	POUND	\$1.00	\$46,966.00	\$0.01	\$0.01	\$0.01
37	40600290	BITUMINOUS MATERIALS (TACK COAT)	8296.00	POUND	\$1.00	\$8,296.00	\$0.01	\$0.01	\$0.01
38	40600370	LONGITUDINAL JOINT SEALANT	21914.00	FOOT	\$3.50	\$76,699.00	\$2.80	\$2.80	\$2.80
39	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	7209.00	TON	\$84.00	\$605,556.00	\$74.00	\$74.00	\$74.00
40	40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	401.00	TON	\$115.00	\$46,115.00	\$142.00	\$142.00	\$142.00
41	40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	2064.00	TON	\$100.00	\$206,400.00	\$82.00	\$82.00	\$82.00
42	42101300	PROTECTIVE COAT	5871.00	SQ YD	\$2.00	\$11,742.00	\$1.90	\$1.90	\$1.90
43	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	19851.00	SQ FT	\$9.50	\$188,584.50	\$8.00	\$8.00	\$8.00
44	42400800	DETECTABLE WARNINGS	480.00	SQ FT	\$41.00	\$19,680.00	\$38.00	\$38.00	\$38.00
45	44000100	PAVEMENT REMOVAL	14700.00	SQ YD	\$15.00	\$220,500.00	\$9.70	\$15.00	\$12.35
46	44000200	DRIVEWAY PAVEMENT REMOVAL	2195.00	SQ YD	\$13.00	\$28,535.00	\$0.01	\$4.50	\$2.26
47	44000300	CURB REMOVAL	105.00	FOOT	\$10.00	\$1,050.00	\$3.20	\$5.00	\$4.10

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extn. Price			
48	44000600	SIDEWALK REMOVAL	297.00	SQ FT	\$3.00	\$891.00	\$0.70	\$1.72	\$1.21
49	44201757	CLASS D PATCHES, TYPE III, 9 INCH	23.00	SQ YD	\$100.00	\$2,300.00	\$200.00	\$200.00	\$200.00
50	48101200	AGGREGATE SHOULDERS, TYPE B	456.00	TON	\$47.00	\$21,432.00	\$52.00	\$52.00	\$52.00
51	50100100	REMOVAL OF EXISTING STRUCTURES	1.00	EACH	\$5,000.00	\$5,000.00	\$0.01	\$1,000.00	\$500.00
52	50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	1.00	EACH	\$480,000.00	\$480,000.00	\$295,000.00	\$350,000.00	\$322,500.00
53	52200700	PRECAST MODULAR RETAINING WALL	3945.00	SQ FT	\$82.00	\$323,490.00	\$68.00	\$68.00	\$68.00
54	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	10.00	EACH	\$2,100.00	\$21,000.00	\$1,880.00	\$2,000.00	\$1,940.00
55	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	8.00	EACH	\$2,300.00	\$18,400.00	\$1,925.00	\$2,100.00	\$2,012.50
56	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	1.00	EACH	\$2,600.00	\$2,600.00	\$2,015.00	\$2,200.00	\$2,107.50
57	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	1.00	EACH	\$2,800.00	\$2,800.00	\$2,600.00	\$2,700.00	\$2,650.00
58	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	3.00	EACH	\$3,100.00	\$9,300.00	\$4,000.00	\$4,250.00	\$4,125.00
59	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	164.00	FOOT	\$57.00	\$9,348.00	\$50.00	\$63.00	\$56.50
60	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	149.00	FOOT	\$62.00	\$9,238.00	\$50.00	\$77.00	\$63.50
61	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	54.00	FOOT	\$70.00	\$3,780.00	\$59.00	\$72.00	\$65.50
62	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	2064.00	FOOT	\$62.00	\$127,968.00	\$41.00	\$63.00	\$52.00
63	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	141.00	FOOT	\$67.00	\$9,447.00	\$60.00	\$84.00	\$72.00
64	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	594.00	FOOT	\$72.00	\$42,768.00	\$51.00	\$72.00	\$61.50
65	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	166.00	FOOT	\$88.00	\$14,608.00	\$62.00	\$98.00	\$80.00
66	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	179.00	FOOT	\$125.00	\$22,375.00	\$126.00	\$174.00	\$150.00
67	55100100	STORM SEWER REMOVAL 4"	32.00	FOOT	\$20.00	\$640.00	\$10.00	\$20.00	\$15.00
68	55100400	STORM SEWER REMOVAL 10"	40.00	FOOT	\$21.00	\$840.00	\$10.00	\$20.00	\$15.00
69	55100500	STORM SEWER REMOVAL 12"	111.00	FOOT	\$22.00	\$2,442.00	\$20.00	\$22.00	\$21.00
70	55100700	STORM SEWER REMOVAL 15"	142.00	FOOT	\$24.00	\$3,408.00	\$20.00	\$22.00	\$21.00
71	55100900	STORM SEWER REMOVAL 18"	153.00	FOOT	\$25.00	\$3,825.00	\$20.00	\$22.00	\$21.00
72	55101200	STORM SEWER REMOVAL 24"	112.00	FOOT	\$30.00	\$3,360.00	\$20.00	\$22.00	\$21.00
73	60100905	PIPE DRAINS 4"	200.00	FOOT	\$40.00	\$8,000.00	\$16.00	\$20.00	\$18.00
74	60100915	PIPE DRAINS 6"	200.00	FOOT	\$45.00	\$9,000.00	\$20.00	\$20.00	\$20.00
75	60108104	PIPE UNDERDRAINS, TYPE 1, 4"	11563.00	FOOT	\$10.00	\$115,630.00	\$6.00	\$6.50	\$6.25
76	60146304	PIPE UNDERDRAINS FOR STRUCTURES 4"	407.00	FOOT	\$36.00	\$14,652.00	\$19.85	\$39.00	\$29.42
77	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	16.00	EACH	\$4,400.00	\$70,400.00	\$3,100.00	\$3,500.00	\$3,300.00
78	60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	1.00	EACH	\$6,200.00	\$6,200.00	\$5,000.00	\$6,400.00	\$5,700.00
79	60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	2.00	EACH	\$2,300.00	\$4,600.00	\$2,000.00	\$2,250.00	\$2,125.00
80	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	5.00	EACH	\$2,300.00	\$11,500.00	\$1,820.00	\$1,900.00	\$1,860.00
81	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	18.00	EACH	\$2,300.00	\$41,400.00	\$2,300.00	\$2,300.00	\$2,300.00
82	60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	1.00	EACH	\$4,400.00	\$4,400.00	\$3,100.00	\$3,400.00	\$3,250.00
83	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	8.00	EACH	\$4,400.00	\$35,200.00	\$3,100.00	\$3,325.00	\$3,212.50
84	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	5.00	EACH	\$5,200.00	\$26,000.00	\$4,200.00	\$5,600.00	\$4,900.00
85	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	2.00	EACH	\$9,000.00	\$18,000.00	\$6,700.00	\$8,650.00	\$7,675.00
86	60500050	REMOVING CATCH BASINS	1.00	EACH	\$775.00	\$775.00	\$600.00	\$650.00	\$625.00
87	60600605	CONCRETE CURB, TYPE B	883.00	FOOT	\$46.00	\$40,618.00	\$44.00	\$48.00	\$46.00
88	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	4039.00	FOOT	\$41.00	\$165,599.00	\$31.00	\$33.00	\$32.00
89	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	3278.00	FOOT	\$46.00	\$150,788.00	\$39.00	\$41.00	\$40.00
90	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	684.00	FOOT	\$42.00	\$28,728.00	\$46.00	\$47.00	\$46.50
91	60619600	CONCRETE MEDIAN, TYPE SB-6.12	348.00	SQ FT	\$21.00	\$7,308.00	\$24.00	\$24.00	\$24.00
92	63200310	GUARDRAIL REMOVAL	31.00	FOOT	\$8.00	\$248.00	\$12.40	\$15.00	\$13.70
93	64200108	SHOULDER RUMBLE STRIPS, 8 INCH	3646.00	FOOT	\$1.00	\$3,646.00	\$1.20	\$1.30	\$1.25
94	66900200	NON-SPECIAL WASTE DISPOSAL	1650.00	CU YD	\$80.00	\$132,000.00	\$0.01	\$55.00	\$27.50
95	66900530	SOIL DISPOSAL ANALYSIS	2.00	EACH	\$1,800.00	\$3,600.00	\$1,450.00	\$1,600.00	\$1,525.00
96	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	1.00	L SUM	\$3,600.00	\$3,600.00	\$4,000.00	\$5,300.00	\$4,650.00
97	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	1.00	L SUM	\$2,000.00	\$2,000.00	\$500.00	\$2,500.00	\$1,500.00
98	66901006	REGULATED SUBSTANCES MONITORING	60.00	CAL DA	\$750.00	\$45,000.00	\$0.01	\$125.00	\$62.50
99	67100100	MOBILIZATION	1.00	L SUM	\$555,000.00	\$555,000.00	\$468,000.00	\$482,000.00	\$475,000.00
100	67201000	SEALING ABANDONED WATER WELLS	2.00	EACH	\$5,200.00	\$10,400.00	\$1,500.00	\$2,600.00	\$2,050.00
101	70107025	CHANGEABLE MESSAGE SIGN	336.00	CAL DA	\$30.00	\$10,080.00	\$27.00	\$27.00	\$27.00
102	70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	178.00	SQ FT	\$1.00	\$178.00	\$2.00	\$2.00	\$2.00
103	70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	16141.00	FOOT	\$0.30	\$4,842.30	\$0.35	\$0.35	\$0.35
104	70300231	TEMPORARY PAVEMENT MARKING - LINE 5"- PAINT	9051.00	FOOT	\$0.35	\$3,167.85	\$0.40	\$0.40	\$0.40

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extn. Price			
105	70300251	TEMPORARY PAVEMENT MARKING - LINE 8"- PAINT	679.00	FOOT	\$0.60	\$407.40	\$0.70	\$0.70	\$0.70
106	70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	1043.00	FOOT	\$1.00	\$1,043.00	\$1.00	\$1.00	\$1.00
107	70307100	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - TYPE IV TAPE	134.00	SQ FT	\$5.00	\$670.00	\$0.38	\$3.75	\$2.06
108	70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	12039.00	FOOT	\$1.00	\$12,039.00	\$0.40	\$0.40	\$0.40
109	70307125	TEMPORARY PAVEMENT MARKING - LINE 5" - TYPE IV TAPE	9051.00	FOOT	\$1.25	\$11,313.75	\$0.50	\$0.50	\$0.50
110	70307140	TEMPORARY PAVEMENT MARKING - LINE 8" - TYPE IV TAPE	679.00	FOOT	\$1.75	\$1,188.25	\$2.40	\$2.40	\$2.40
111	70307160	TEMPORARY PAVEMENT MARKING - LINE 12"- TYPE IV TAPE	1043.00	FOOT	\$2.50	\$2,607.50	\$3.60	\$3.60	\$3.60
112	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	30.00	EACH	\$50.00	\$1,500.00	\$40.00	\$40.00	\$40.00
113	72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	10.00	EACH	\$100.00	\$1,000.00	\$50.00	\$50.00	\$50.00
114	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	1.00	EACH	\$150.00	\$150.00	\$150.00	\$150.00	\$150.00
115	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	1.00	EACH	\$250.00	\$250.00	\$200.00	\$200.00	\$200.00
116	72800100	TELESCOPING STEEL SIGN SUPPORT	34.00	FOOT	\$20.00	\$680.00	\$20.00	\$20.00	\$20.00
117	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	134.00	SQ FT	\$6.00	\$804.00	\$6.00	\$6.00	\$6.00
118	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	2446.00	FOOT	\$1.00	\$2,446.00	\$1.00	\$1.00	\$1.00
119	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	3808.00	FOOT	\$1.25	\$4,760.00	\$1.25	\$1.25	\$1.25
120	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	951.00	FOOT	\$2.50	\$2,377.50	\$3.00	\$3.00	\$3.00
121	78004620	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 4"	8987.00	FOOT	\$5.00	\$44,935.00	\$4.00	\$4.00	\$4.00
122	78004625	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 5"	5243.00	FOOT	\$6.00	\$31,458.00	\$4.25	\$4.25	\$4.25
123	78004640	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 8"	679.00	FOOT	\$9.00	\$6,111.00	\$8.00	\$8.00	\$8.00
124	78004660	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 12"	92.00	FOOT	\$15.00	\$1,380.00	\$12.00	\$12.00	\$12.00
125	78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12" GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	594.00	FOOT	\$10.00	\$5,940.00	\$4.00	\$4.00	\$4.00
126	78011000	GROOVING FOR RECESSED PAVEMENT MARKING 5"	158.00	SQ FT	\$6.00	\$948.00	\$3.00	\$3.00	\$3.00
127	78011025	GROOVING FOR RECESSED PAVEMENT MARKING 5"	8987.00	FOOT	\$0.60	\$5,392.20	\$0.45	\$0.45	\$0.45
128	78011030	GROOVING FOR RECESSED PAVEMENT MARKING 6"	7380.00	FOOT	\$0.65	\$4,797.00	\$0.50	\$0.50	\$0.50
129	78011045	GROOVING FOR RECESSED PAVEMENT MARKING 9"	679.00	FOOT	\$2.50	\$1,697.50	\$1.00	\$1.00	\$1.00
130	78011065	GROOVING FOR RECESSED PAVEMENT MARKING 13"	980.00	FOOT	\$3.25	\$3,185.00	\$1.25	\$1.25	\$1.25
131	78300201	PAVEMENT MARKING REMOVAL - GRINDING	25.00	SQ FT	\$2.50	\$62.50	\$5.00	\$5.00	\$5.00
132	80400100	ELECTRIC SERVICE INSTALLATION	2.00	EACH	\$4,000.00	\$8,000.00	\$4,068.71	\$5,014.00	\$4,541.36
133	80400200	ELECTRIC UTILITY SERVICE CONNECTION	1.00	L SUM	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00
134	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	2589.00	FOOT	\$22.50	\$58,252.50	\$23.13	\$31.10	\$27.12
135	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	150.00	FOOT	\$33.00	\$4,950.00	\$38.74	\$54.30	\$46.52
136	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	400.00	FOOT	\$36.00	\$14,400.00	\$40.41	\$63.30	\$51.86
137	81400100	HANDHOLE	4.00	EACH	\$1,900.00	\$7,600.00	\$2,363.00	\$3,362.61	\$2,862.80
138	81400200	HEAVY-DUTY HANDHOLE UNIT DUCT, 600V, 4-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	4.00	EACH	\$4,200.00	\$16,800.00	\$3,807.44	\$5,249.00	\$4,528.22
139	81603096	UNIT DUCT, 600V, 4-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	3809.00	FOOT	\$16.00	\$60,944.00	\$16.99	\$25.70	\$21.34
140	81603100	UNIT DUCT, 600V, 4-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	3699.00	FOOT	\$19.00	\$70,281.00	\$19.17	\$28.10	\$23.64
141	81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	160.00	FOOT	\$13.00	\$2,080.00	\$11.07	\$14.90	\$12.98
142	81800240	AERIAL CABLE, 2-1/C NO. 8 WITH MESSENGER WIRE	6840.00	FOOT	\$5.00	\$34,200.00	\$1.50	\$1.70	\$1.60
143	82110004	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION D	25.00	EACH	\$750.00	\$18,750.00	\$694.70	\$711.99	\$703.34
144	82110006	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION F	17.00	EACH	\$750.00	\$12,750.00	\$690.82	\$760.30	\$725.56
145	82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	1.00	EACH	\$57,500.00	\$57,500.00	\$16,024.11	\$51,871.00	\$33,947.56
146	83057175	LIGHT POLE, WOOD, 35 FOOT, CLASS 3, WITH 15FT MAST ARM	2.00	EACH	\$2,100.00	\$4,200.00	\$1.00	\$519.00	\$260.00
147	83057215	LIGHT POLE, WOOD, 40 FOOT, CLASS 3, WITH 15FT MAST ARM	40.00	EACH	\$2,300.00	\$92,000.00	\$1.00	\$519.00	\$260.00
148	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	420.00	FOOT	\$310.00	\$130,200.00	\$358.30	\$429.07	\$393.68
149	83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	28.00	EACH	\$725.00	\$20,300.00	\$635.59	\$980.00	\$807.80
150	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	43.00	EACH	\$525.00	\$22,575.00	\$1.00	\$181.00	\$91.00
151	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	5037.00	FOOT	\$1.00	\$5,037.00	\$1.10	\$2.21	\$1.66
152	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	486.00	FOOT	\$4.50	\$2,187.00	\$5.30	\$6.15	\$5.72
153	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	546.00	FOOT	\$2.60	\$1,419.60	\$2.70	\$5.08	\$3.89
154	87800100	CONCRETE FOUNDATION, TYPE A	12.00	FOOT	\$260.00	\$3,120.00	\$299.29	\$346.80	\$323.04

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extn'd. Price			
155	A2002016	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2" CALIPER, BALLED AND BURLAPPED	3.00	EACH	\$850.00	\$2,550.00	\$680.00	\$680.00	\$680.00
156	A2002924	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 3" CALIPER, BALLED AND BURLAPPED	13.00	EACH	\$850.00	\$11,050.00	\$590.00	\$590.00	\$590.00
157	A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	4.00	EACH	\$850.00	\$3,400.00	\$587.50	\$587.50	\$587.50
158	A2005024	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 3" CALIPER, BALLED AND BURLAPPED	10.00	EACH	\$850.00	\$8,500.00	\$642.50	\$642.50	\$642.50
159	A2005116	TREE, JUGLANS NIGRA (BLACK WALNUT), 2" CALIPER, BALLED AND BURLAPPED	3.00	EACH	\$850.00	\$2,550.00	\$612.50	\$612.50	\$612.50
160	A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	8.00	EACH	\$850.00	\$6,800.00	\$575.00	\$575.00	\$575.00
161	A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	22.00	EACH	\$850.00	\$18,700.00	\$575.00	\$575.00	\$575.00
162	A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	7.00	EACH	\$850.00	\$5,950.00	\$575.00	\$575.00	\$575.00
163	A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	26.00	EACH	\$850.00	\$22,100.00	\$575.00	\$575.00	\$575.00
164	A2007624	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 3" CALIPER, BALLED AND BURLAPPED	17.00	EACH	\$850.00	\$14,450.00	\$700.00	\$700.00	\$700.00
165	LC100101	UTILITY MONITORING	25000.00	UNIT	\$1.00	\$25,000.00	\$1.00	\$1.00	\$1.00
166	LC200051	REJECTED LOAD TRANSPORTATION	10.00	LOAD	\$300.00	\$3,000.00	\$0.01	\$60.00	\$30.00
167	LC200200	TREE, SPECIAL	16.00	EACH	\$850.00	\$13,600.00	\$592.50	\$592.50	\$592.50
168	LC200320	SHRUB, SPECIAL	40.00	EACH	\$90.00	\$3,600.00	\$53.83	\$53.83	\$53.83
169	LC200321	SHRUB, SPECIAL I	117.00	EACH	\$90.00	\$10,530.00	\$66.25	\$66.25	\$66.25
170	LC200322	SHRUB, SPECIAL II	26.00	EACH	\$90.00	\$2,340.00	\$70.00	\$70.00	\$70.00
171	LC200323	SHRUB, SPECIAL III	12.00	EACH	\$90.00	\$1,080.00	\$69.00	\$69.00	\$69.00
172	LC200360	PERENNIAL PLANTINGS, SPECIAL I	946.00	EACH	\$18.00	\$17,028.00	\$14.30	\$14.30	\$14.30
173	LC200361	PERENNIAL PLANTINGS, SPECIAL II	88.00	EACH	\$18.00	\$1,584.00	\$12.94	\$12.94	\$12.94
174	LC200362	PERENNIAL PLANTINGS, SPECIAL III	116.00	EACH	\$18.00	\$2,088.00	\$13.00	\$13.00	\$13.00
175	LC200363	PERENNIAL PLANTINGS, SPECIAL IV	659.00	EACH	\$18.00	\$11,862.00	\$21.00	\$21.00	\$21.00
176	LC200364	PERENNIAL PLANTINGS, SPECIAL V	522.00	EACH	\$18.00	\$9,396.00	\$16.10	\$16.10	\$16.10
177	LC200365	PERENNIAL PLANTINGS, SPECIAL VI	1608.00	UNIT	\$18.00	\$28,944.00	\$11.06	\$11.06	\$11.06
178	LC200366	PERENNIAL PLANTINGS, SPECIAL VII	50.00	UNIT	\$18.00	\$900.00	\$16.10	\$16.10	\$16.10
179	LC200367	PERENNIAL PLANTINGS, SPECIAL VIII	40.00	UNIT	\$18.00	\$720.00	\$13.00	\$13.00	\$13.00
180	LC200501	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	39155.00	UNIT	\$1.00	\$39,155.00	\$1.00	\$1.00	\$1.00
181	LC351001	AGGREGATE BASE COURSE, TYPE B 2.5"	1590.00	SQ YD	\$6.00	\$9,540.00	\$1.50	\$3.25	\$2.38
182	LC442009	TACTILE DIRECTIONAL INDICATOR	342.00	SQ FT	\$40.00	\$13,680.00	\$36.00	\$36.00	\$36.00
183	LC500230	GRATING FOR CONCRETE FLARED END SECTION 24"	1.00	EACH	\$1,600.00	\$1,600.00	\$650.00	\$1,115.00	\$882.50
184	LC500234	GRATING FOR CONCRETE FLARED END SECTION 36"	3.00	EACH	\$1,800.00	\$5,400.00	\$1,100.00	\$2,625.00	\$1,862.50
185	LC500418	CAST-IN-PLACE CONCRETE WALL CAP	365.00	FOOT	\$210.00	\$76,650.00	\$312.00	\$312.00	\$312.00
186	LC600029	PERFORATED RISER PIPE	3.00	EACH	\$4,100.00	\$12,300.00	\$5,000.00	\$5,100.00	\$5,050.00
187	LC600200	INSTALL SURVEY MONUMENTS	2.00	EACH	\$575.00	\$1,150.00	\$500.00	\$550.00	\$525.00
188	LC800266	TEMPORARY LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION D	25.00	EACH	\$775.00	\$19,375.00	\$50.00	\$230.00	\$140.00
189	LC800267	TEMPORARY LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION F	17.00	EACH	\$925.00	\$15,725.00	\$55.00	\$230.00	\$142.50
190	X0324597	CLOSED CIRCUIT TELEVISION CABINET	2.00	EACH	\$8,250.00	\$16,500.00	\$12,748.91	\$13,443.00	\$13,095.96
191	X0326898	CENTER LINE - RUMBLE STRIP - 16"	1068.00	FOOT	\$1.30	\$1,388.40	\$3.00	\$4.09	\$3.54
192	X0327349	TEMPORARY WOOD POLE, 40 FT., CLASS 4	1.00	EACH	\$2,100.00	\$2,100.00	\$519.00	\$1,915.33	\$1,217.16
193	X0426200	DEWATERING	1.00	L SUM	\$35,000.00	\$35,000.00	\$27,000.00	\$150,000.00	\$88,500.00
194	X0488100	REMOVING EXISTING SEPTIC TANK	2.00	EACH	\$5,000.00	\$10,000.00	\$1,300.00	\$2,000.00	\$1,650.00
195	X1400007	FIBER OPTIC CABLE IN CONDUIT, 24 FIBERS, SINGLE MODE	5083.00	FOOT	\$4.00	\$20,332.00	\$4.20	\$4.21	\$4.20
196	X1400102	OUTDOOR RATED NETWORK CABLE	147.00	FOOT	\$3.50	\$514.50	\$3.15	\$4.20	\$3.68
197	X1400150	SERVICE INSTALLATION, GROUND MOUNTED, METERED	1.00	EACH	\$2,500.00	\$2,500.00	\$3,772.58	\$3,841.00	\$3,806.79
198	X1400216	LAYER II (DATALINK) SWITCH	2.00	EACH	\$5,500.00	\$11,000.00	\$4,671.44	\$5,293.00	\$4,982.22
199	X1700112	BRICK PAVEMENT REMOVAL	542.00	SQ FT	\$10.00	\$5,420.00	\$1.58	\$2.00	\$1.79
200	X2070304	POROUS GRANULAR EMBANKMENT (SPECIAL)	2668.00	CU YD	\$56.00	\$149,408.00	\$44.00	\$57.00	\$50.50
201	X2130010	EXPLORATION TRENCH (SPECIAL)	300.00	FOOT	\$25.00	\$7,500.00	\$16.00	\$20.00	\$18.00
202	X2200018	ORNAMENTAL FENCE	365.00	FOOT	\$210.00	\$76,650.00	\$123.91	\$123.91	\$123.91
203	X2800500	INLET PROTECTION (SPECIAL)	7.00	EACH	\$290.00	\$2,030.00	\$150.00	\$350.00	\$250.00
204	X3110102	COARSE AGGREGATE BACKFILL (SPECIAL)	1811.00	CU YD	\$40.00	\$72,440.00	\$0.10	\$55.00	\$27.55

Item No.	Pay Code	Description	Quantity	Unit	Eng Unit Price		Min. Bid Price	Max. Bid Price	Avg. Bid Price
					Unit Price	Extn. Price			
205	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	4.00	EACH	\$1,000.00	\$4,000.00	\$500.00	\$1,000.00	\$750.00
206	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	2.00	EACH	\$1,500.00	\$3,000.00	\$500.00	\$1,700.00	\$1,100.00
207	X4023000	TEMPORARY ACCESS (ROAD)	3.00	EACH	\$5,000.00	\$15,000.00	\$1,000.00	\$3,100.00	\$2,050.00
208	X5020100	AGGREGATE COLUMN GROUND IMPROVEMENT MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	1.00	L SUM	\$260,000.00	\$260,000.00	\$260,000.00	\$305,000.00	\$282,500.00
209	X6020096	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	3.00	EACH	\$15,000.00	\$45,000.00	\$16,000.00	\$17,000.00	\$16,500.00
210	X6700405	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	18.00	CAL MO	\$4,000.00	\$72,000.00	\$2,500.00	\$4,000.00	\$3,250.00
211	X7010216	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	1.00	L SUM	\$285,000.00	\$285,000.00	\$63,000.00	\$190,300.00	\$126,650.00
212	X7800815	TEMPORARY ELECTRIC SERVICE INSTALLATION	606.00	FOOT	\$0.50	\$303.00	\$5.00	\$5.00	\$5.00
213	X8040104	LUMINAIRE SHIELD	1.00	EACH	\$2,000.00	\$2,000.00	\$1,150.00	\$4,586.21	\$2,868.10
214	X8210405	TEMPORARY LIGHTING CONTROLLER	2.00	EACH	\$500.00	\$1,000.00	\$209.44	\$270.50	\$239.97
215	X8250060	LIGHT POLE (SPECIAL)	1.00	EACH	\$10,000.00	\$10,000.00	\$1.00	\$519.00	\$260.00
216	X8300001	RELOCATE EXISTING LUMINAIRE	40.00	EACH	\$11,500.00	\$460,000.00	\$9,593.59	\$10,193.00	\$9,893.30
217	X8440102	MAILBOX REMOVAL AND RELOCATION	42.00	EACH	\$525.00	\$22,050.00	\$83.00	\$458.28	\$270.64
218	XX000856	PRECONSTRUCTION VIDEO TAPING	4.00	EACH	\$475.00	\$1,900.00	\$400.00	\$400.00	\$400.00
219	XX003668	REMOTE CONTROLLED VIDEO SYSTEM	1.00	L SUM	\$8,000.00	\$8,000.00	\$1,495.00	\$2,400.00	\$1,947.50
220	XX005940	FURNISH WITNESS POST	2.00	EACH	\$6,000.00	\$12,000.00	\$7,135.00	\$8,238.61	\$7,686.80
221	XX006522	STAMPED COLORED PORTLAND CEMENT CONCRETE MEDIAN SURFACE 4 INCH (SPECIAL)	46.00	EACH	\$180.00	\$8,280.00	\$50.00	\$150.00	\$100.00
222	XX006652	FLOCCULATION LOGS	4217.00	SQ FT	\$21.00	\$88,557.00	\$15.00	\$15.55	\$15.28
223	XX006658	FLOCCULATION POWDER	10.00	EACH	\$120.00	\$1,200.00	\$1.00	\$1.00	\$1.00
224	XX006659	STAMPED COLORED PORTLAND CEMENT CONCRETE	10.00	POUND	\$20.00	\$200.00	\$1.00	\$1.00	\$1.00
225	XX006898	CATCH BASINS, SPECIAL	7828.00	SQ FT	\$26.00	\$203,528.00	\$23.00	\$24.35	\$23.68
226	XX008824	PERMEABLE PLASTIC BERM	8.00	EACH	\$3,100.00	\$24,800.00	\$1,100.00	\$1,850.00	\$1,475.00
227	XX008865	LIGHT POLE, SPECIAL, TYPE 2	574.00	FOOT	\$16.00	\$9,184.00	\$15.00	\$18.00	\$16.50
228	XX009135	PAVEMENT MARKING REMOVAL (SPECIAL)	2.00	EACH	\$11,000.00	\$22,000.00	\$9,720.00	\$10,091.54	\$9,905.77
229	XX009142	BUILDING REMOVAL NO. 1	9414.00	SQ FT	\$1.00	\$9,414.00	\$0.60	\$0.60	\$0.60
230	Z0007601	BUILDING REMOVAL NO. 2	1.00	L SUM	\$50,000.00	\$50,000.00	\$22,000.00	\$50,000.00	\$36,000.00
231	Z0007602	BUILDING REMOVAL NO. 3	1.00	L SUM	\$25,000.00	\$25,000.00	\$15,000.00	\$30,000.00	\$22,500.00
232	Z0007603	BUILDING REMOVAL NO. 4	1.00	L SUM	\$5,000.00	\$5,000.00	\$7,000.00	\$20,000.00	\$13,500.00
233	Z0007604	STABILIZED CONSTRUCTION ENTRANCE	1.00	L SUM	\$25,000.00	\$25,000.00	\$14,000.00	\$30,000.00	\$22,000.00
234	Z0013797	CONSTRUCTION LAYOUT	311.00	SQ YD	\$40.00	\$12,440.00	\$25.00	\$40.00	\$32.50
235	Z0013798	DUST CONTROL WATERING	1.00	UNIT	\$100,000.00	\$100,000.00	\$47,000.00	\$83,000.00	\$65,000.00
236	Z0019600	FENCE REMOVAL	100.00	FOOT	\$100.00	\$10,000.00	\$1.00	\$100.00	\$50.50
237	Z0022800	TEMPORARY INFORMATION SIGNING	2780.00	FOOT	\$5.00	\$13,900.00	\$4.50	\$4.93	\$4.72
238	Z0030850	TEMPORARY CONSTRUCTION FENCE	150.00	SQ FT	\$16.00	\$2,400.00	\$20.00	\$20.00	\$20.00
239	Z0055905	TEMPORARY TRAFFIC SIGNAL TIMING	2000.00	FOOT	\$3.50	\$7,000.00	\$3.81	\$4.00	\$3.90
240	Z0073510		5.00	EACH	\$1,250.00	\$6,250.00	\$500.00	\$1,436.00	\$968.00
Total						\$9,859,570.15			